RESPONSIBILITY SCHEDULE

ANNOTATIONS: O: OWNER (LIMITED BRANDS OR VENDOR) G: GENERAL CONTRACTOR L: LANDLORD E: EXISTING

STOREFRONT- VSL

Item	Furnished By O	Furnished By G	Furnished By L	Installed By O	Installed By G	Installed By L	E	Remarks
PRE-FINISHED METAL TRIM / DECORATIVE PROFILES	●				●			
PRE-FINISHED BREAK METAL	●				●			
PRE-FINISHED METAL BASE	●				●			
SIGNAGE	●			●				
PRE-FINISHED METAL MULLIONS	●				●			
STOREFRONT GLAZING, U.O.N.	●				●			VSL SIDE ONLY
MARKETING GRID	●				●			
WINDOW LIGHT BOX TOWER (LBTXX)	●				●			G.C. TO ASSEMBLE, SEE ELECTRIC DWGS FOR POWER.
WALL MOUNTED LIGHTBOX (LBWXX)	●				●			G.C. TO ASSEMBLE, SEE ELECTRIC DWGS FOR POWER.
~~REVEALS AT NEUTRAL PIERS & BULKHEAD~~	●				●			~~VSL SIDE ONLY WHEN REQUIRED~~
PORTAL LIGHT BOX	●				●			POWER AND BLOCKING BY G.C.
LAMINATED RIBBON PATTERN GLASS W/ OPACICOAT	●				●			
BLACK CHERRY GLASS W/ OPACICOAT	●				●			
STOREFRONT VITRINES	●				●			

SALES AREA- VSL/VSB

Item	Furnished By O	Furnished By G	Furnished By L	Installed By O	Installed By G	Installed By L	E	Remarks
BEAUTY SHELF LIGHTING	●				●			
9-NICHE FOCAL	●				●			INSTALL LOOSE FABRIC PANELS
FRAMED GRAPHICS	●				●			
SCRIPT SIGNAGE VINYLS	●			●				
RIBBON WRAPPED VALANCE PANELS AT BRA SALON	●				●			WITH PRE-INSTALLED HARDWARE
RECESSED STANDARD WALL PANELS	●				●			
DECORATIVE LAMPS / CASHWRAP LAMPS	●				●			
DRUM SHADE	●				●			
CRYSTAL KNOBS AT COLUMNS	●				●			INSTALL W/ VENDOR SUPPLIED HARDWARE

FITTING ROOMS- VSL

Item	Furnished By O	Furnished By G	Furnished By L	Installed By O	Installed By G	Installed By L	E	Remarks
FITTING ROOM MIRROR DECORATIVE FRAME, MOUNTING FRAME, BACK PANEL, AND GLASS	●				●			G.C. TO PROVIDE BLOCKING
FITTING ROOM HOOKS	●				●			G.C. TO PROVIDE BLOCKING
GO BACK NICHE/CLOSET	●				●			
GO BACK RACK	●				●			
FREESTANDING BRA WARDROBER	●				●			G.C. TO SECURE TO WALL.
FITTING ROOM SEATING	●				●			
~~DRAPERY, TIE-BACK & ROD~~	●				●			

STOREFRONT - PINK

VOID

Item	Furnished By O	Furnished By G	Furnished By L	Installed By O	Installed By G	Installed By L	E	Remarks
MARKETING PIPE RAILS - PIPES AND FITTINGS		●			●			G.C. TO FIELD PAINT
PINK SIGNAGE: PREFINISHED PLANKS	●				●			ASSEMBLE PER MFG. INSTRUCTIONS
PINK SIGNAGE: "PINK" LETTERS	●			●				
WOOD WINDOW MULLIONS	●				●			PRE-PRIMED, PAINTED BY G.C
AZEK BASE	●				●			
HEX TILE AT PINK STOREFRONT ENTRY	●				●			THINSET AND GROUT BY G.C.
PREFINISHED PINK WOOD PLANK PANEL (W/ DOG)	●				●			ASSEMBLE PER MFG. INSTRUCTIONS
STOREFRONT GLAZING, U.O.N.		●			●			
WINDOW VINYL LOGO AND BORDER	●			●				
THIN BRICK, MORTAR AND INSTALLATION ACCESSORIES	●				●			SEE STOREFRONT A08.XX SERIES
DECORATIVE PAINT BRICK FINISH	●			●				**NOTE: ARCHITECT TO CONFIRM RESPONSIBILITY W/ DESIGNER**
ROUND PILASTER TRIM (AND 5" DOG)	●				●			
REVEALS AT NEUTRAL PIERS & BULKHEAD		●			●			
1/4" (MASONITE), 3/8" AND 3/4" HDF PANELS		●			●			
BLIND DOOR MIRROR: LADDER FRAME, PLY BACKER, J-CHANNELS, SUB-FRAME, AND DECORATIVE FRAME	●				●			
BLIND DOOR MIRROR GLASS, MASTIC AND PRIMER		●			●			

SALES AREA - PINK

VOID

Item	Furnished By O	Furnished By G	Furnished By L	Installed By O	Installed By G	Installed By L	E	Remarks
BARRISTER CABINET MIRRORED TRANSOM AT FITTING ROOM / ALCOVE TRANSITION	●				●			GLASS COMES PRE-INSTALLED
BARRISTER CABINETS INCLUDING MIRRORED VALANCE	●				●			GLASS COMES PRE-INSTALLED
ACCESSORY CABINETS	●				●			PRE-FINISHED
PUCK PANELS	●				●			
PINK FOCAL CABINETS	●				●			PRE-FINISHED
NEON SIGNAGE	●			●				
SUPPORT & POWER FOR NEON SIGNAGE		●			●			
BULB LETTER SIGNAGE	●			●				
SUPPORT & POWER FOR BULB LETTER SIGNAGE		●			●			
SCRIPT LETTER SIGNAGE	●			●				
SUPPORT & POWER FOR SCRIPT LETTER SIGNAGE		●			●			
BACKWRAP MIRROR: 3/4" PLYWOOD MIRROR BACKER, PRIMER & MASTIC		●			●			
BACKWRAP MIRROR TILES AND GOLD LEAF FRAME	●				●			
ILLUMINATED BACKWRAP "PINK" LETTERS	●			●				
POWER FOR BACKWRAP LETTERS		●			●			
BACKWRAP CUBBIES	●				●			
LADDER RAIL PIPE AND BRACKETS	●				●			PRE-FINISHED
BRASS HOOKS AND HARNESS HOOKS	●				●			
MARKETING PIPE RAILS - PIPES AND FITTINGS		●			●			G.C. TO FIELD PAINT
DECORATIVE SALES FLOOR MIRROR: INCLUDES GLASS, PLYWOOD BACKER, J-CHANELS, MASTIC, AND Z-CLIPS	●				●			THIS DOES NOT INCLUDE DOOR MIRRORS
VIDEO MONITOR BACKWRAP	●			●				
VIDEO MONITOR BACKWRAP/GOLD LEAF FRAME	●				●			
PRE-PRINTED WALLCOVERING GRAPHICS	●				●			
APPLIED VINYL GRAPHICS	●			●				
FIELD PAINTED BOUNDARY STRIPE APPLIED OVER WALLCOVERING @ CASHWRAP AND POWDER ROOM		●			●			APPLY USING OWNER SUPPLIED STENCIL AND INSTRUCTIONS
FIELD PAINTED LOVE PINK TEXT AT ROOM #2	●			●				
FIELD PAINTED STENCILS THROUGHOUT SALES AREA	●			●				WHEN APPLIED OVER PAINTED GYP. BD. OR TRIM, G.C. TO APPLY PRIMER BEHIND STENCIL, SEE SPECIFICATIONS 099000

FITTING ROOMS - PINK

VOID

Item	Furnished By O	Furnished By G	Furnished By L	Installed By O	Installed By G	Installed By L	E	Remarks
FITTING ROOM SEATING	●				●			
ALL FITTING ROOM TRIM	●				●			
FIT CARD HOLDER	●				●			
PAPER PANTY HOLDER	●				●			
WALLCOVERING GRAPHIC PANELS	●				●			SEE SHEET A07.XX AND J/A10.09
FITTING ROOM MIRROR: LADDER FRAME, PLY BACKER, J-CHANNELS, SUB-FRAME, AND DECORATIVE FRAME	●				●			
FITTING ROOM MIRROR GLASS, MASTIC AND PRIMER		●			●			THIS DOES NOT INCLUDE DOOR TYPE 'A' (PRE-INSTALLED)
BUILT-IN BRA WARDROBER	●				●			PRE-FINISHED
OUTFITTING CENTER	●				●			PRE-FINISHED
GO-BACK CLOSET	●				●			PRE-FINISHED
MIRROR TRANSOM FOR TRANSITION FROM SALES TO FITTING ROOM ALCOVE	●				●			
FITTING ROOM BENCH	●				●			
PINK FITTING ROOM HOOKS	●				●			G.C. TO PROVIDE BLOCKING
FIELD PAINTED BOUNDARY STRIPE / 'PINK' LOGO OVER WALLCOVERING AT FRS, ALCOVE, AND VESTIBULES		●			●			APPLY USING OWNER SUPPLIED STENCIL AND INSTRUCTIONS
FIELD PAINTED FITTING ROOM GRAPHICS OVERLAPPING TRIM - (PKGA)	●			●				
WALLCOVERING FITTING ROOM GRAPHICS CUT-OFF BY TRIM - (PKGB)	●				●			

STOREFRONT- GLOBAL

Item	Furnished By O	Furnished By G	Furnished By L	Installed By O	Installed By G	Installed By L	E	Remarks
~~EXTERIOR WATERPROOFING AND FLASHING~~		●			●			
~~BLADE SIGN~~	●			●				~~BLOCKING BY G.C.~~
~~STOREFRONT AWNINGS~~	●			●				~~BLOCKING BY G.C.~~
~~STOREFRONT BANNER~~	●			●				~~BLOCKING BY G.C.~~
~~IN-WALL BATT INSULATION~~		●			●			
STOREFRONT STRUCTURAL MEMBERS		●			●			SEE STRUCTURAL DRAWINGS
MALL FLOORING AT STOREFRONT		●			●			SEE FLOOR AND WALL FINISH PLAN
~~WALK-OFF ENTRY MAT~~		●			●			~~SEE SPECIFICATIONS SECTION 124813~~
~~CONCRETE SIDEWALK~~							●	~~PER LL REQUIREMENTS~~
~~CONCRETE SIDEWALK PATCH AND REPAIR~~		●			●			~~AS REQUIRED~~
~~UV PROTECTION FILM~~		●			●			~~REFER TO SPECIFICATIONS SECTION 088100~~
~~IMPACT RESISTANT METAL MULLIONS~~		●			●			~~FOR USE IN HURRICANE ZONES~~

SALES AREA - GLOBAL

Item	Furnished By O	Furnished By G	Furnished By L	Installed By O	Installed By G	Installed By L	E	Remarks
CASHWRAPS, CASHWRAP FILLERS & BACKWRAPS	●				●			FILLER AS REQUIRED
ANTI-FATIGUE MAT AT CASHWRAP	●				●			
CASHWRAP EQUIPMENT, DETAGGERS, AND SIGNATURE CAPTURE.	●			●				
FURNITURE, FIXTURES & PRESENTATION ITEMS	●				●			G.C. TO UNCRATE, ASSEMBLE AND CLEAN
CABINETWORK (PRE-FINISHED) & ACCESSORIES	●				●			
FINS / GABLES	●				●			
WOOD TRIMS	●				●			SEE DETAILS J/A10.01 AND J/A11.01
FABRICS AND MOUNTING HARDWARE	●				●			
WALL MOUNTED HANGBARS AND BRACKETS	●				●			
INTERIOR SIGNAGE ELEMENTS	●			●				

NON-SALES STOCKROOM

Item	Furnished By O	Furnished By G	Furnished By L	Installed By O	Installed By G	Installed By L	E	Remarks
VCT FLOORING AND RUBBER BASE		●			●			
SURFACE MOUNTED STANDARDS, BRACKETS, LADDER HOOKS, CLIPS, MOUNTING HARDWARE, ETC.	●				●			
HANGROD, BRACKETS, END CAPS, CONNECTORS FOR NON-SALES	●				●			
3/4" WALL MOUNTED WOOD SHELVING		●			●			
FIXED RIVET RACK SHELVING AND HARDWARE	●				●			
MOBILE SHELVING AND HARDWARE	●				●			
MOBILE SHELVING CRANK SYSTEM	●				●			
BRUSHED STAINLESS STEEL CORNER GUARDS		●			●			REFER TO A/A13.01 PURCHASED THROUGH CBC
DRAWING PLAN TUBE		●			●			
MARKETING STORAGE BINS		●			●			
HARDWARE STORAGE BINS		●			●			
PROCESSING WORK STATION	●				●			PROVIDED BY LLS
~~STORAGE LEDGE SIGNAGE~~		●			●			

BREAK ROOMS/AREAS

REFER TO A/A13.01 FOR SPECS AND RESPONSIBILITIES

TOILET/POWDER ROOMS

REFER TO A/A13.01 FOR SPECS AND RESPONSIBILITIES

OFFICE/TRAINING ROOMS

REFER TO A/A13.01 FOR SPECS AND RESPONSIBILITIES

GENERAL

Item	Furnished By O	Furnished By G	Furnished By L	Installed By O	Installed By G	Installed By L	E	Remarks
GYPSUM BOARD: CEILINGS, WALLS, ETC. AND REQUIRED FRAMING & BLOCKING		●			●			SEE SPECIFICATIONS SECTION 092900 & 092950
CONCEALED IN-WALL WOOD OR METAL BLOCKING FOR ALL ITEMS IN STORE		●			●			F.R.T. AS REQUIRED
PAINT		●			●			
DOORS, FRAMES & HARDWARE								SEE DOOR SCHEDULE A/A00.02
DOOR CHIMES	●				●			
LAY-IN CEILING (TILE & GRID)		●			●			SEE SPECIFICATIONS SECTION 095123
FIRE EXTINGUISHERS		●			●			SEE SPECIFICATIONS
EXIT & EMERGENCY LIGHTS	●				●			
CEILING AND WALL ACCESS PANELS		●			●			SEE SPECIFICATIONS SECTION 083100
FIBERGLASS REINFORCED PANELS (F.R.P.)		●			●			
ALL FURRING		●			●			
FLOOR PROTECTION DURING CONSTRUCTION		●			●			1/8" MASONITE
SAW CUTTING / TRENCHING/ CORE DRILLING		●			●			WHERE REQUIRED PER EQUIPMENT SPECIFIED
MUSIC / VIDEO SYSTEM SUPPORT		●			●			
IP CAMERA CABINET SUPPORT		●			●			
SECURITY MONITOR STRUCTURAL SUPPORT		●			●			
SECURITY DOMES	●			●				
ZINC DIVIDER STRIP		●			●			
STUB-UP PRE-WIRING		●			●			
ALL MIRRORS		●			●			UNLESS OTHERWISE NOTED
MIRROR J-CHANNELS AND BACKING		●			●			UNLESS OTHERWISE NOTED
MIRROR MASTIC		●			●			
TILE FLOORING AND WALL FINISHES	●				●			
ALL NATURAL STONE FINISHES	●				●			
GROUT, SEALANT, THINSET, AND MORTAR		●			●			UNLESS OTHERWISE NOTED
DEMISING WALL FRAMING			●			●		
DEMISING WALL GYP. BD.		●			●			
FLOOR PREPARATION & LEVELING		●			●			AS REQUIRED
CONCRETE SLAB		●			●			AS REQD, COORDINATE W/ LANDLORD
FIRE PATCHING / FIREPROOFING		●			●			AS REQD BY CODE / TENANT CRITERIA
WALL COVERINGS	●				●			
WOOD FLOORING	●				●			SEE SPECIFICATIONS SECTION 096429
WOOD FLOORING VAPOR BARRIER AND ADHESIVE		●			●			SEE SPECIFICATIONS SECTION 096429
WOOD FLOORING MOISTURE TEST		●			●			SEE SPECIFICATIONS SECTION 096429
~~EXPANSION JOINT COVERS~~		●			●			
~~CURTAIN TRACK, FABRIC, AND TIE-BACK HOOK~~	●				●			
CARPET	●				●			
CARPET BINDER BAR EDGE STRIPS		●			●			
CARPET SHIELD		●			●			
SOUND ATTENUATION INSULATION		●			●			SEE WALL SCHEDULE

DEMOLITION

Item	Furnished By O	Furnished By G	Furnished By L	Installed By O	Installed By G	Installed By L	E	Remarks
								INCLUDES: BARRICADE AND PHASING
BARRICADE PANEL (STRUCTURE)		●			●			
~~BARRICADE GRAPHICS - FULL BLEED (PKG 1, 1+, PINK FREESTANDING)~~	●			●				~~REQUIRES L.L. APPROVAL~~
BARRICADE GRAPHICS - PARTIAL BLEED (PKG II)	●				●			REQUIRES L.L. APPROVAL
PAINT FINISH		●			●			
TEMPORARY POWER SETUP		●			●			
DE-INSTALLATION AND DE-BRANDING		●			●			SEE P/A00.00
BARRICADE REMOVAL					●			
~~CHAIN LINK FENCE (IF REQUIRED)~~		●			●			
~~SURFACE MOUNTED STANDARDS FOR PHASED STORES~~	●				●			
~~TEMPORARY PRE-FAB FITTING ROOMS FOR PHASED STORES~~	●				●			

ELECTRICAL

ELECTRICAL WORK (AS SPECIFIED) — SEE ELECTRICAL DRAWINGS

FIRE ALARM

FIRE ALARM WORK (AS SPECIFIED) — SEE ELECTRICAL DRAWINGS

MECHANICAL

MECHANICAL WORK (AS SPECIFIED) — SEE MECHANICAL DRAWINGS

PLUMBING

PLUMBING WORK (AS SPECIFIED) — SEE PLUMBING / FIRE PROTECTION DRAWINGS

FIRE PROTECTION

FIRE PROTECTION WORK (AS SPECIFIED) — SEE PLUMBING / FIRE PROTECTION DRAWINGS

STRUCTURAL

STRUCTURAL WORK (AS SPECIFIED) — SEE STRUCTURAL DRAWINGS

NO SCALE

-

A

SHREMSHOCK
Shremshock Architects, Inc.
6130 S. Sunbury Rd. Westerville, OH 43081
t: 614 545 4550 | f: 614 545 4555 | shremshock.com
Gerald S. Shremshock, Architect
Timothy J. Shremshock, Architect

Limitedbrands
LIMITED STORE PLANNING, INC.
d/b/a STORE DESIGN & CONSTRUCTION
Three Limited Parkway · Columbus, Ohio 43230
Telephone: 614.415.7000 · Fax: 614.415.7349

PROHIBITION ON REUSE:
THESE DRAWINGS AND SPECIFICATIONS WERE PREPARED FOR USE ON A SPECIFIC SITE CONTEMPORANEOUSLY WITH THEIR ISSUE DATE. THEY ARE NOT INTENDED FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. REUSE OF THESE DRAWINGS AND SPECIFICATIONS, OR ANY REPRODUCTION THEREOF, ON ANOTHER PROJECT IS PROHIBITED AND CONTRARY TO LAW UNLESS EXPRESSLY AUTHORIZED IN WRITING BY LIMITED STORE PLANNING, INC., D/B/A LIMITED STORE DESIGN AND CONSTRUCTION ("LSDC").

THESE DRAWINGS AND SPECIFICATIONS ARE THE PROPERTY OF LSDC AND SHALL NOT BE DISPLAYED IN ANY MANNER OR USED ON ANY OTHER PROJECT EXCEPT BY WRITTEN AGREEMENT WITH LSDC. NO REPRODUCTION OF THESE DRAWINGS AND SPECIFICATIONS SHALL BE MADE WITHOUT THE WRITTEN AUTHORIZATION OF THE LSDC. ALL ORIGINALS OR REPRODUCTIONS OF THESE DRAWINGS AND SPECIFICATIONS MUST BE RETURNED TO LSDC UPON COMPLETION OF THEIR INTENDED USE, UNLESS OTHERWISE AGREED BY THE LSDC.

COPYRIGHT NOTICE:
THESE DRAWINGS AND SPECIFICATIONS ARE COPYRIGHTED AND SUBJECT TO COPYRIGHT PROTECTION AS AN "ARCHITECTURAL WORK" UNDER SEC. 102 OF THE COPYRIGHT ACT, 17 U.S.C. AS AMENDED DECEMBER 1990; KNOWN AS THE ARCHITECTURAL WORKS COPYRIGHT PROTECTION ACT OF 1990. THE PROTECTION INCLUDES, WITHOUT LIMITATION, THE OVERALL FORM, ARRANGEMENT AND COMPOSITION OF SPACES, AND ELEMENTS OF THE DESIGN. UNDER SUCH PROTECTION, UNAUTHORIZED USE OF THESE DRAWINGS AND SPECIFICATIONS MAY RESULT IN CESSATION OF CONSTRUCTION, BUILDING SEIZURE, AND/OR MONETARY LIABILITY.

PROJECT INFORMATION:
010500295
VICTORIA'S SECRET
PARK PLAZA MALL
6000 W. MARKHAM STREET
SPACE# 2050
LITTLE ROCK, AR 72205

SCOPE:	FULL REMODEL	PACKAGE:	PGK 2
DESIGN TYPE:	NMA	GENERATION:	FALL 2014 (141Fa)
LSD&C PROJECT #:	00059784	A/E PROJECT #:	140153

REVISIONS:
REQUIRED BY: DATE

ELITE CONSTRUCTION GROUP
LAKE JACKSON, TX
PHONE: 979-285-0712
NOTE: THESE PRINTS HAVE BEEN REDUCED BY 50 PERCENT. SCALE WILL BE 50 PERCENT OF WHAT IS NOTED ON PLANS

DATE ISSUED: 05/23/2014
DESIGNED BY: LC
DRAWN BY: LMR
CHECKED BY: JRM

RESPONSIBILITY SCHEDULE

DRAWING NUMBER:
A00.01