



NO SCALE	D 09.12.
05N-A0004-D00-NOTE	

1. ELECTRICAL CONTRACTOR IS TO TILT THE LAMP IN ALL AIM-ABLE FIXTURES AT A 30 DEGREE ANGLE TOWARD HALL OR CABLETRAY PER DIRECTION FROM THE L5DC PROJECT MANAGER PRIOR TO STORE OPENING - REFER TO "DIRECTION ARROWS" ON PLAN
2. IF MUSIC SPEAKERS NEED TO BE RELOCATED OTHER THAN WHAT IS SHOWN ON REFLECTED CLG. PLAN, THEN RELOCATE AS CLOSE AS POSSIBLE TO GIVEN LOCATION. RELOCATE IN A SYMMETRICAL PATTERN IN RELATIONSHIP TO ADJACENT LIGHTS AND SPRINKLER HEADS.
3. G.C. IS TO PROVIDE ACCESS PANELS AS REQUIRED BY LANDLORD TO GAIN ACCESS TO PULL BOXES, DAMPERS, VALVES, TEMPERATURE CONTROL, COORDINATE ACCESS TO BE HANDLED WITH L5DC - LOCATE IN SYMMETRICAL PATTERN WITH LIGHTING LAYOUT) SEE ACCESS PANEL SPECIFICATIONS.
4. ALL DIMENSIONS SHOWN ON REFLECTED CEILING PLAN ARE TO FACE OF GYP.BD OR TO FACE OF FINISH U.O.N. SEE CONSTRUCTION DETAILS FOR CLARIFICATION.
5. NO COMBUSTIBLE MATERIALS OF ANY TYPE ALLOWED ABOVE FINISHED CEILING OR IN ANY OTHER CONCEALED OR NON SPRINKLED SPACE.
6. WHEN A LEDGE IS LOCATED ABOVE THE MANAGER'S OFFICE OR ABOVE THE LAVATORIES, G.C. IS RESPONSIBLE TO MAKE SURE THESE LEDGES ARE KEPT CLEAR OF ALL CONDUIT AND OTHER ITEMS THAT MAY RUN ABOVE, IF IT IS NECESSARY TO RUN CONDUIT OR OTHER ITEMS, HOLD THEM TIGHT TO FULL HEIGHT WALLS TO ALLOW USE OF LEDGE. SEE REFLECTED CEILING PLAN FOR EXTENT OF LEDGE.
7. ALL CEILING HEIGHTS ARE FROM THE TOP OF FINISH FLOOR TO UNDERSIDE OF FINISH CEILING
8. PROVIDE ADEQUATE CLEARANCES FOR FIXTURES, DUCTS, CEILINGS AND RELATED PERTINENT ITEMS NECESSARY TO MAINTAIN THE SPECIFIED HEIGHTS ABOVE FINISH FLOOR.
9. ALL EXIT SIGNS ARE TO BE CEILING MOUNTED U.O.N.

NO SCALE	C 0912
05N-A0004-C00-NOTE	

ABV	ABOVE	GA	GAUGE	(R)	RELOCATED
ACT	ACoustICAL CEILING TILE	G.C.	GENERAL CONTRACTOR	RAD	RADIUS
A.F.F.	ABOVE FINISH FLOOR	GYP BD	GYPsUM BOARD	REQD	REQUIRED
AFR	ACCESSIBLE FITTING ROOM			(REF)	REFERENCE
ALUM	ALUMINUM	HDF	HIGH DENSITY FIBERBOARD	RGS	REGISTERS
A.W.I.	AMERICAN WOOD INSTITUTE	HGT	HEIGHT	R.O.	ROUGH OPENING
ASTM	AMERICAN SOCIETY FOR TESTING AND MATERIALS	HORIZ	HORIZONTAL		
		H.M.	HOLLOW METAL	S.C.	SOLID CORE
BBW	BATH AND BODY WORKS	HR	HOUR	SECT	SECTION
BD	BOARD	HVAC	HEATING, VENTILATION, AIR CONDITIONING	SHT	SHEET
BLKG	BLOCKING			SIM	SIMILAR
B.O.	BOTTOM OF	I.D.	INSIDE DIMENSION	SPL	SPECIAL
B5	BRA SALON	IFS	INTEGRATED FACILITY SYSTEM	SQ	SQUARE
BW	BACKDRAp	IN	INCHES	S.F.	SQUARE FEET
		INCD	INCANDESCENT	S.S.	STAINLESS STEEL
CBPB	CEMENT BONDED PARTICLE BOARD	INT	INTERIOR	SSHA	STEEL STUD MANUFACTURERS ASSOC
C / CL	CENTERLINE	INV	LAVATORY	STC	SOUND TRANSMISSION COEFFICIENT
CLG	CEILING	L	LANDLORD	STL	STEEL
C.M.	CONSTRUCTION MANAGER	L.L.	LEASE LINE	STRUCT	STRUCTURE
COL	COLUMN	LLS	LIMITED LOGISTIC SERVICES	SURF	SURFACE
CONC	CONCRETE	LSDC	LIMITED STORE DESIGN & CONSTRUCTION	TEMP	TEMPERATURE
CONSTR	CONSTRUCTION	LTS	LIMITED TECHNOLOGY SERVICES	THRU	THROUGH
C.T.F.	CUT TO FIT	MAX	MAXIMUM	T.O.P.	TOP OF
CW	CASHDRAp	MDF	MEDIUM DENSITY FIBERBOARD	TRANS	TRANSITION
C/C	CENTER TO CENTER	MECH	MECHANICAL	TYP	TYPICAL
DIAG	DIAGONAL	MFG	MANUFACTURER	U.L.	UNDERWRITERS LABORATORIES
DIA.	DIAMETER	MISC	MISCELLANEOUS	U.N.O.	UNLESS NOTED OTHERWISE
EA	EACH	MIN	MINIMUM	U.O.N.	UNLESS OTHERWISE NOTED
EIFS	EXTERIOR INSULATION FINISH SYSTEM	MTD	MOUNTED	V.C.	VOLUME CONTROL
ELEV	ELEVATION	MTL	METAL	VERT	VERTICAL
E.P.A.	ENVIRONMENTAL PROTECTION AGENCY	N/A	NOT APPLICABLE	V.I.F.	VERIFY IN FIELD
EQ	EQUAL	N.I.C.	NOT IN CONTRACT	VSL	VICTORIA'S SECRET LINGERIE
(E)	EXISTING	N.P.	NEUTRAL PIER	VSS	VICTORIA'S SECRET
EXT	EXTERIOR	(N)	NEA	W/	WITH
		N.O.	NOT TO SCALE	W/O	WOOD WITHOUT
F.C.D.	FINISHED CABINET DIMENSION	O.C.	ON CENTER	W.I.C.	WOOD INSTITUTE COUNCIL
FD	FLOOR DRAIN	O.D.	OUTSIDE DIMENSION		
F.F.	FINISH DIMENSION	OPG	OPENING		
F.H.	FLAT HEAD	OPF	OPPOSITE		
FHSDS	FLAT HEAD SELF DRILLING SCREW	PKG	PACKAGE		
FIN	FINISH	PL	PLATE		
FL	FLOOR	PLEX	PLEXIGLASS		
FLG	FLOORING	PLYMD	PLYWOOD		
FLUOR	FLUORESCENT	PRE-FIN	PRE-FINISHED		
F.O.	FINISHED OPENING	PM	PROJECT MANAGER		
FR	FITTING ROOM	P.T.	PRESSURE TREATED		
F.R.P.	FIBERGLASS REINFORCED PANELS	QTY	QUANTITY		
F.R.T.	FIRE RESISTIVE TREATED FT				

RECEIVED BY: DATE:

ELITE CONSTRUCTION GROUP
LAKE JACKSON, TX
PHONE: 979-285-0712

NOTE: THESE PRINTS HAVE BEEN
REDUCED BY 50 PERCENT. SCALE
WILL BE 50 PERCENT OF WHAT IS
NOTED ON PLANS

DATE ISSUED: 09-05-2014

DRAWN BY: APL

CHECKED BY: ANW

DATE: 09-05-2014

BY: AJD

DRAWING NUMBER:

NO SCALE	A 09.12
05N-A0004-A00-NOTE	

A00.04