

ABBREVIATIONS, RESPONSIBILITY SCHEDULES			
FPC	FIRE PROTECTION CONTRACTOR	LD	LIGHTING PACKAGE DISTRIBUTOR
AHJ	AUTHORITY HAVING JURISDICTION	LL	LANDLORD
GC	GENERAL CONTRACTOR	LSD&C	LIMITED STORE DESIGN & CONSTRUCTION
LC	LANDLORD CONTRACTOR	MC	MECHANICAL CONTRACTOR

ABBREVIATIONS - PLUMBING					
AD	ACCESS DOOR	G	GAS	PM	PROJECT MANAGER
ADD	AMERICAN DISABILITY ACT	GAL	GALLONS	POC	POINT OF CONNECTION
AF	ABOVE FINISHED FLOOR	GC	GENERAL CONTRACTOR	PRV	PRESSURE REDUCING VALVE
AFP	ACCESS PANEL	GPB	GALLONS PER MINUTE	PSI	POUNDS PER SQUARE INCH
CD	CEILING DIFFUSER OR CONDENSATE DRAIN	HB	HOSE BIBB	(R)	RELOCATE
CFM	CUBIC FEET PER MINUTE	HP	HORSEPOWER	RPBP	REDUCED PRESSURE BACKFLOW PREVENTER
CI	COLD IRON	HW	HOT WATER		RPVM
CO	CLEANOUT	INV	INVERT		REHABILITATION PER MINUTE
CONT	CONTINUE				
CONTR	CONTRACTOR	LAV	LAVATORY	SCH	SCHEDULE
COTG	CLEANOUT TO GRADE	LB	POUND	SOV	SHUT-OFF VALVE OR SCHEDULE OF VALVE
CW	COLD WATER	LF	LINEAL FEET		
DET	DETAIL			UH	UNIT HEATER
DF	DRINKING FOUNTAIN	MECH	MECHANICAL	UON	UNLESS OTHERWISE NOTED
DL	DOOR	MFR	MANUFACTURER	UTR	UP THRU ROOF
DS	DREASTCAMER	MTD	MOUNTED		
DTR	DOWN THRU ROOF	MTR	MOTOR	VTR	VENT THRU ROOF
DWG	DRAWING				
(E)	EXISTING	(N)	NEW	WC	WATER CLOSET
EW	ELECTRIC WATER COOLER	N.C.	NORMALLY CLOSED	WCO	WALL CLEANOUT
		N.I.C.	NOT IN CONTRACT	WG	WATER GAUGE
FCU	FLOOR CLEANOUT	N/O	NORMALLY OPEN	WH	WATER HEATER
FCU	FAN COIL UNIT	N/A	NOT APPLICABLE	WH	WATER HAMMER ARRESTER
FD	FLOOR DRAIN	N/A	NOT TO SCALE	WT	WEIGHT
FDC	FURNISHED BY OWNER, INSTALLED BY CONTRACTOR	P	PUMP		
FFC	FIRE PROTECTION CONTRACTOR	P	PLUMBING CONTRACTOR		
FFS	FEET PER SECOND	PD	PRESSURE DROP		
FSL	FLOOR SINK	PLBG	PLUMBING		

THIS SET IS PART OF THE CONSTRUCTION DOCUMENTS, OTHER SHEETS INCLUDING PLANS, DETAILS AND SPECIFICATIONS APPLY. THAT SHOW HEREON IS SCHEMATIC IN NATURE AND NOT TO BE USED AS A SHOP DRAWING; THEREFORE, INCLUDE ALL MODIFICATIONS REQUIRED TO CONFORM TO THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL VERIFY THE LOCATION AND DIMENSIONS OF ALL ARCHITECTURAL AND STRUCTURAL ELEMENTS AS SHOWN ON THEIR RESPECTIVE DOCUMENTS, THESE ELEMENTS ARE SHOWN FOR REFERENCE AND SHALL BE VERIFIED PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE ACCURACY OF THESE ELEMENTS, NO DESIGN RESPONSIBILITY IS ASSUMED. FOR ANY PORTION OF THE WORK THAT THE PROFESSIONAL ENGINEER HAS NOT SIGNED AND SEALED PER STATE OR PROVINCE REQUIREMENTS.

PLUMBING FIXTURE SCHEDULE-VS/PINK	NIS	E
	05N-P0101-E00-SCHD	

NEITHER OTHERWISE SPECIFIED, CONTRACTOR SHALL PROVIDE ALL NECESSARY EQUIPMENT, MATERIAL, LABOR AND SUPERVISION NECESSARY TO COMPLETE THE PLUMBING WORK IN ACCORDANCE WITH THE SPECIFICATIONS AND STANDARDS.

FIELD VERIFY EXIST SILE AND LOCATION OF EXISTING WASTE PIPING BELOW SLAB, WASTE PIPING ABOVE CEILING AND UP THROUGH ROOF AND COLD WATER SUPPLY PIPING ABOVE CEILING PRIOR TO COMMENCEMENT OF ANY WORK. AFTER INSTALLATION AND FINAL CONNECTION OF NEW WASTE PIPING BELOW SLAB, BACK FILL AND PATCH IN ACCORDANCE WITH THE LANDLORD'S CRITERIA REGARDING SUCH WORK.

CONTRACTOR SHALL FURNISH AND INSTALL ALL OF THE NECESSARY PLUMBING FIXTURES (SEE PLUMBING RESPONSIBILITY SCHEDULE ON THIS SHEET) TO SERVE THE TENANT'S DEMISED PREMISES AND MAKE NECESSARY INSTALLATION OF DOMESTIC WATER AND SEWER PIPING FROM TENANT'S DEMISED PREMISE TO CONNECTION PROVIDED BY LANDLORD.

SANITARY VENTS SHALL BE ROUTED TO THE EXISTING LANDLORD'S POINT OF CONNECTION WITHIN THE TENANT'S DEMISED PREMISES OR TO A POINT APPROVED BY LOCAL AUTHORITY. THE CONTRACTOR SHALL PROVIDE A CAPPED TEE FOR POSSIBLE FUTURE CONNECTION (IF REQUIRED BY THE LANDLORD). CONTRACTOR SHALL COORDINATE ALL ROOF PENETRATIONS WITH THE LANDLORD'S ROOFING CONTRACTOR, AS REQUIRED. WENT THRU ROOF SHALL BE AT LEAST 15 FEET AWAY FROM A/C UNIT FRESH AIR INTAKE.

SEAL AROUND ALL PIPES PENETRATING FIRE SEPARATIONS WITH LISTED AND APPROVED FIRE SEAL MATERIAL. ONLY LISTED AND APPROVED SEALANTS AND METHODS FOR THE SPECIFIC USE WILL BE PERMITTED.

THE CONTRACTOR SHALL INSTALL ALL TOILET FIXTURES IN ACCORDANCE WITH ALL CODES AND AS REQUIRED BY LANDLORD'S CRITERIA. CONTROLS FOR FLUSH VALVES SHALL BE MOUNTED ON THE WIDE SIDE OF THE WATER CLOSET AND NO MORE THAN 44" A.F.F.

THE CONTRACTOR SHALL ENSURE THAT ALL SLAB PENETRATIONS WITHIN THE TENANT'S DEMISED PREMISES ARE PROPERLY SEALED AND REMAIN WATER TIGHT TO PREVENT ANY POSSIBLE DAMAGE TO OTHER TENANTS AND/OR TO THE BUILDING. FAILURE TO DO SO SHALL BE AT THE RISK AND SOLE EXPENSE OF THE CONTRACTOR.

ALL MATERIAL SHALL BE NEW AND OF COMMERCIAL GRADE, AND BEAR UNDERWRITER'S LABORATORIES AND UNION LABELS WHERE SUCH LABELING APPLIES.

PLUMBING CONTRACTOR TO FIELD VERIFY PROPER SLOPE OF EXISTING SEWER TO MAIN SEWER PRIOR TO ANY NEW PLUMBING INSTALLATION.

PLUMBING CONTRACTOR MUST VISIT THE JOBSITE TO BECOME FAMILIAR WITH MAJOR ITEMS SUCH AS STRUCTURAL ELEMENTS AND OTHER EXISTING JOB CONDITIONS THAT MAY AFFECT THE WORK. ADDITIONALLY, PLUMBING CONTRACTOR SHALL VERIFY EXIST LOCATIONS AND DIMENSIONS OF SUCH ITEMS AS WASTE, VENTS, WATER LINES, ETC.

PLUMBING CONTRACTOR TO FAMILIARIZE AND FOLLOW SPECIFICATIONS AND DETAILS CONTAINED IN DESIGN CRITERIA OF TENANT HANDBOOK.

PLUMBING CONTRACTOR TO CLEAR ALL EXISTING AND NEW DRAIN LINES AND FIXTURES, PRIOR TO TURNING OVER SPACE TO TENANT.

PLUMBING CONTRACTOR SHALL PROVIDE ACCESS TO VALVES, TRAP PRIMERS, ETC. INSTALLED BEHIND WALLS, FLOORS OR CEILINGS.

NO PVC PLUMBING ALLOWED WITHIN CEILING VOIDS USED FOR NON-DUCTED RETURN AIR PLENUM OR IN WALLS, EXCEPT IN CANADA WHERE XFR-PVC MAY BE USED IF PERMITTED BY THE AUTHORITY HAVING JURISDICTION.

THE GENERAL CONTRACTOR'S FIRE SPRINKLER SUB-CONTRACTOR SHALL DESIGN AND INSTALL FIRE SPRINKLER SYSTEM CONFORMING TO LANDLORD'S CRITERIA, TENANT'S REQUIREMENTS, AND PER LOCAL CODES AND NFPA STANDARDS.

 **LARSON BINKLEY**

Larson Binkley, Inc. T 816-997-9601
310 W 20th Street, Suite 200 F 816-997-9602
Kansas City, Missouri 64108 larsonbinkley.com

Limited brands

LIMITED STORE PLANNING, INC.
d/b/a STORE DESIGN & CONSTRUCTION
Three Limited Parkway • Columbus, Ohio 43230
Telephone: 614.415.7000 • Fax: 614.415.7349

PROJECT INFORMATION: 010501726

PINK VICTORIA'S SECRET

FAYETTE MALL
 3401 NICHOLASVILLE RD
 SPACE # 11-904
 LEXINGTON, KY 40503

SCOPE: NEW / PACKAGE: A
 DESIGN TYPE: PINK GENERATION: 15159
 LSOWC PROJECT #: 00653007 A/E PROJECT #: 20140334

REVISIONS:

REQUIRED BY:	DATE
ELITE CONSTRUCTION GROUP LAKE JACKSON, TX PHONE: 979-285-0712 NOTE: THESE PRINTS HAVE BEEN REDUCED BY 50 PERCENT. SCALE WILL BE 50 PERCENT OF WHAT IS NOTED ON PLANS	
DATE ISSUED:	09-05-2014
DESIGNED BY:	JES
DRAWN BY:	JES
CHECKED BY:	NRF

**PLUMBING
NOTES AND
SCHEDULES**

DRAWING NUMBER:
P01.01