STOREFRONT - PINK

STOREFRONT - PINK	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
MARKETING PIPE RAILS - PIPES AND FITTINGS		●			●			G.C. TO FIELD PAINT
PINK SIGNAGE: PREFINISHED PLANKS	●				●			ASSEMBLE PER MFG. INSTRUCTIONS
PINK SIGNAGE: "PINK" LETTERS	●			●				
WOOD WINDOW MULLIONS	●				●			PRE-PRIMED, PAINTED BY G.C.
AZEK BASE	●				●			
HEX TILE AT PINK STOREFRONT ENTRY	●				●			THINSET AND GROUT BY G.C.
PREFINISHED PINK WOOD PLANK PANEL (W/ DOG)	●				●			ASSEMBLE PER MFG. INSTRUCTIONS
STOREFRONT GLAZING, U.O.N.		●			●			
WINDOW VINYL LOGO AND BORDER	●			●				
THIN BRICK, MORTAR AND INSTALLATION ACCESSORIES	●				●			SEE STOREFRONT A08.XX SERIES
DECORATIVE PAINT BRICK FINISH	●			●				
ROUND PILASTER TRIM (AND 5" DOG)	●				●			
REVEALS AT NEUTRAL PIERS & BULKHEAD		●			●			
1/4" (MASONITE), 3/8" AND 3/4" HDF PANELS		●			●			
BLIND DOOR MIRROR: LADDER FRAME, PLY BACKER, J-CHANNELS, SUB-FRAME, AND DECORATIVE FRAME	●				●			
BLIND DOOR MIRROR GLASS, MASTIC AND PRIMER		●			●			

SALES AREA - PINK

SALES AREA - PINK	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
BARRISTER CABINET MIRRORED TRANSOM AT FITTING ROOM / ALCOVE TRANSITION	●				●			GLASS COMES PRE-INSTALLED
BARRISTER CABINETS INCLUDING MIRRORED VALANCE	●				●			GLASS COMES PRE-INSTALLED
ACCESSORY CABINETS	●				●			PRE-FINISHED
PUCK PANELS	●				●			
PINK FOCAL CABINETS	●				●			PRE-FINISHED
NEON SIGNAGE	●			●				
SUPPORT & POWER FOR NEON SIGNAGE		●			●			
BULB LETTER SIGNAGE	●			●				
SUPPORT & POWER FOR BULB LETTER SIGNAGE		●			●			
SCRIPT LETTER SIGNAGE	●			●				
SUPPORT & POWER FOR SCRIPT LETTER SIGNAGE		●			●			
BACKWRAP MIRROR: 3/4" PLYWOOD MIRROR BACKER, PRIMER & MASTIC		●			●			
BACKWRAP MIRROR TILES AND GOLD LEAF FRAME	●				●			
ILLUMINATED BACKWRAP "PINK" LETTERS	●			●				
POWER FOR BACKWRAP LETTERS		●			●			
BACKWRAP CUBBIES	●				●			
LADDER RAIL PIPE AND BRACKETS	●				●			PRE-FINISHED
BRASS HOOKS AND HARNESS HOOKS	●				●			
MARKETING PIPE RAILS - PIPES AND FITTINGS		●			●			G.C. TO FIELD PAINT
DECORATIVE SALES FLOOR MIRROR: INCLUDES GLASS, PLYWOOD BACKER, J-CHANELS, MASTIC, AND Z-CLIPS	●				●			THIS DOES NOT INCLUDE DOOR MIRRORS
VIDEO MONITOR BACKWRAP	●			●				
VIDEO MONITOR BACKWRAP GOLD LEAF FRAME	●				●			
PRE-PRINTED WALLCOVERING GRAPHICS	●				●			
APPLIED VINYL GRAPHICS	●			●				
FIELD PAINTED BOUNDARY STRIPE APPLIED OVER WALLCOVERING @ CASHWRAP AND POWDER ROOM		●			●			APPLY USING OWNER SUPPLIED STENCIL AND INSTRUCTIONS
FIELD PAINTED LOVE PINK TEXT AT ROOM #2	●			●				
FIELD PAINTED STENCILS THROUGHOUT SALES AREA	●			●				WHEN APPLIED OVER PAINTED GYP. BD. OR TRIM, G.C. TO APPLY PRIMER BEHIND STENCIL, SEE SPECIFICATIONS 099000

FITTING ROOMS - PINK

FITTING ROOMS - PINK	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
FITTING ROOM SEATING	●				●			
ALL FITTING ROOM TRIM	●				●			
FIT CARD HOLDER	●				●			
PAPER PANTY HOLDER	●				●			
WALLCOVERING GRAPHIC PANELS	●				●			SEE SHEET A07.XX AND J/A10.09
FITTING ROOM MIRROR: LADDER FRAME, PLY BACKER, J-CHANNELS, SUB-FRAME, AND DECORATIVE FRAME	●				●			
FITTING ROOM MIRROR GLASS, MASTIC AND PRIMER		●			●			THIS DOES NOT INCLUDE DOOR TYPE 'A' (PRE-INSTALLED)
BUILT-IN BRA WARDROBER	●				●			PRE-FINISHED
OUTFITTING CENTER	●				●			PRE-FINISHED
GO-BACK CLOSET	●				●			PRE-FINISHED
MIRROR TRANSOM FOR TRANSITION FROM SALES TO FITTING ROOM ALCOVE	●				●			
FITTING ROOM BENCH	●				●			
PINK FITTING ROOM HOOKS	●				●			G.C. TO PROVIDE BLOCKING
FIELD PAINTED BOUNDARY STRIPE / 'PINK' LOGO OVER WALLCOVERING AT FRS, ALCOVE, AND VESTIBULES		●			●			APPLY USING OWNER SUPPLIED STENCIL AND INSTRUCTIONS
FIELD PAINTED FITTING ROOM GRAPHICS OVERLAPPING TRIM - (PKGA)	●			●				
WALLCOVERING FITTING ROOM GRAPHICS CUT-OFF BY TRIM - (PKGB)	●				●			

STOREFRONT- GLOBAL

STOREFRONT- GLOBAL	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
EXTERIOR WATERPROOFING AND FLASHING		●			●			
BLADE SIGN	●			●				BLOCKING BY G.C.
STOREFRONT AWNINGS	●			●				BLOCKING BY G.C.
STOREFRONT BANNER	●			●				BLOCKING BY G.C.
IN-WALL BATT INSULATION		●			●			
STOREFRONT STRUCTURAL MEMBERS		●			●			SEE STRUCTURAL DRAWINGS
MALL FLOORING AT STOREFRONT		●			●			SEE FLOOR AND WALL FINISH PLAN
WALK-OFF ENTRY MAT		●			●			SEE SPECIFICATIONS SECTION 124813
CONCRETE SIDEWALK							●	PER LL REQUIREMENTS
CONCRETE SIDEWALK PATCH AND REPAIR		●			●			AS REQUIRED
UV PROTECTION FILM		●			●			REFER TO SPECIFICATIONS SECTION 088100
IMPACT RESISTANT METAL MULLIONS		●			●			FOR USE IN HURRICANE ZONES

SALES AREA - GLOBAL

SALES AREA - GLOBAL	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
CASHWRAPS, CASHWRAP FILLERS & BACKWRAPS	●				●			FILLER AS REQUIRED
ANTI-FATIGUE MAT AT CASHWRAP	●				●			
CASHWRAP EQUIPMENT, DETAGGERS, AND SIGNATURE CAPTURE.	●			●				
FURNITURE, FIXTURES & PRESENTATION ITEMS	●				●			G.C. TO UNCRATE, ASSEMBLE AND CLEAN
CABINETWORK (PRE-FINISHED) & ACCESSORIES	●				●			
FINS / GABLES	●				●			
WOOD TRIMS	●				●			SEE DETAILS J/A10.01 AND J/A11.01
FABRICS AND MOUNTING HARDWARE	●				●			
WALL MOUNTED HANGBARS AND BRACKETS	●				●			
INTERIOR SIGNAGE ELEMENTS	●			●				

NON-SALES STOCKROOM

NON-SALES STOCKROOM	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
VCT FLOORING AND RUBBER BASE		●			●			
SURFACE MOUNTED STANDARDS, BRACKETS, LADDER HOOKS, CLIPS, MOUNTING HARDWARE, ETC.	●				●			
HANGROD, BRACKETS, END CAPS, CONNECTORS FOR NON-SALES	●				●			
3/4" WALL MOUNTED WOOD SHELVING		●			●			
FIXED RIVET RACK SHELVING AND HARDWARE	●				●			
MOBILE SHELVING AND HARDWARE	●				●			
MOBILE SHELVING CRANK SYSTEM	●				●			
BRUSHED STAINLESS STEEL CORNER GUARDS		●			●			REFER TO A/A13.01 PURCHASED THROUGH CBC
DRAWING PLAN TUBE		●			●			
MARKETING STORAGE BINS		●			●			
HARDWARE STORAGE BINS		●			●			
PROCESSING WORK STATION	●				●			PROVIDED BY LLS
STORAGE LEDGE SIGNAGE		●			●			

BREAK ROOMS/AREAS

REFER TO A/A13.01 FOR SPECS AND RESPONSIBILITIES

TOILET/POWDER ROOMS

REFER TO A/A13.01 FOR SPECS AND RESPONSIBILITIES

OFFICE/TRAINING ROOMS

REFER TO A/A13.01 FOR SPECS AND RESPONSIBILITIES

GENERAL

GENERAL	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
GYPSUM BOARD: CEILINGS, WALLS, ETC. AND REQUIRED FRAMING & BLOCKING		●			●			SEE SPECIFICATIONS SECTION 092900 & 092950
CONCEALED IN-WALL WOOD OR METAL BLOCKING FOR ALL ITEMS IN STORE		●			●			F.R.T. AS REQUIRED
PAINT		●			●			
DOORS, FRAMES & HARDWARE								SEE DOOR SCHEDULE A/A00.02
DOOR CHIMES	●				●			
LAY-IN CEILING (TILE & GRID)		●			●			SEE SPECIFICATIONS SECTION 095123
FIRE EXTINGUISHERS		●			●			SEE SPECIFICATIONS
EXIT & EMERGENCY LIGHTS	●				●			
CEILING AND WALL ACCESS PANELS		●			●			SEE SPECIFICATIONS SECTION 083100
FIBERGLASS REINFORCED PANELS (F.R.P.)		●			●			
ALL FURRING		●			●			
FLOOR PROTECTION DURING CONSTRUCTION		●			●			1/8" MASONITE
SAW CUTTING / TRENCHING/ CORE DRILLING		●			●			WHERE REQUIRED PER EQUIPMENT SPECIFIED
MUSIC / VIDEO SYSTEM SUPPORT		●			●			
IP CAMERA CABINET SUPPORT		●			●			
SECURITY MONITOR STRUCTURAL SUPPORT		●			●			
SECURITY DOMES	●			●				
ZINC DIVIDER STRIP		●			●			
STUB-UP PRE-WIRING		●			●			
ALL MIRRORS		●			●			UNLESS OTHERWISE NOTED
MIRROR J-CHANNELS AND BACKING		●			●			UNLESS OTHERWISE NOTED
MIRROR MASTIC		●			●			
TILE FLOORING AND WALL FINISHES	●				●			
ALL NATURAL STONE FINISHES	●				●			
GROUT, SEALANT, THINSET, AND MORTAR		●			●			UNLESS OTHERWISE NOTED
DEMISING WALL FRAMING			●			●		
DEMISING WALL GYP. BD.		●			●			
FLOOR PREPARATION & LEVELING		●			●			AS REQUIRED
CONCRETE SLAB		●			●			AS REQD, COORDINATE W/ LANDLORD
FIRE PATCHING / FIREPROOFING		●			●			AS REQD BY CODE / TENANT CRITERIA
WALL COVERINGS	●				●			
WOOD FLOORING	●				●			SEE SPECIFICATIONS SECTION 096429
WOOD FLOORING VAPOR BARRIER AND ADHESIVE		●			●			SEE SPECIFICATIONS SECTION 096429
WOOD FLOORING MOISTURE TEST		●			●			SEE SPECIFICATIONS SECTION 096429
EXPANSION JOINT COVERS		●			●			
CURTAIN TRACK, FABRIC, AND TIE-BACK HOOK	●				●			
CARPET	●				●			
CARPET BINDER BAR EDGE STRIPS		●			●			
CARPET SHIELD		●			●			
SOUND ATTENUATION INSULATION		●			●			SEE WALL SCHEDULE
THERMAL BATT INSULATION		●			●			

DEMOLITION

DEMOLITION	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	INCLUDES: BARRICADE AND PHASING
BARRICADE PANEL (STRUCTURE)		●			●			
BARRICADE GRAPHICS - FULL BLEED (PKG I, I+, PINK FREESTANDING)	●			●				REQUIRES L.L. APPROVAL
BARRICADE GRAPHICS - PARTIAL BLEED (PKG II)	●				●			REQUIRES L.L. APPROVAL
PAINT FINISH		●			●			
TEMPORARY POWER SETUP		●			●			
DE-INSTALLATION AND DE-BRANDING		●			●			SEE P/A00.00
BARRICADE REMOVAL					●			
CHAIN LINK FENCE (IF REQUIRED)		●			●			
SURFACE MOUNTED STANDARDS FOR PHASED STORES	●				●			
TEMPORARY PRE-FAB FITTING ROOMS FOR PHASED STORES	●				●			

ELECTRICAL

ELECTRICAL WORK (AS SPECIFIED) — SEE ELECTRICAL DRAWINGS

FIRE ALARM

FIRE ALARM WORK (AS SPECIFIED) — SEE ELECTRICAL DRAWINGS

MECHANICAL

MECHANICAL WORK (AS SPECIFIED) — SEE MECHANICAL DRAWINGS

PLUMBING

PLUMBING WORK (AS SPECIFIED) — SEE PLUMBING / FIRE PROTECTION DRAWINGS

FIRE PROTECTION

FIRE PROTECTION WORK (AS SPECIFIED) — SEE PLUMBING / FIRE PROTECTION DRAWINGS

STRUCTURAL

STRUCTURAL WORK (AS SPECIFIED) — SEE STRUCTURAL DRAWINGS

RESPONSIBILITY SCHEDULE

ANNOTATIONS: O: OWNER (LIMITED BRANDS OR VENDOR) G: GENERAL CONTRACTOR L: LANDLORD E: EXISTING

NO SCALE

-

A

GreenbergFarrow
1430 West Peachtree Street NW
Suite 200
Atlanta, GA 30309
t: 404 601 4000 f: 404 601 3970

Limitedbrands
LIMITED STORE PLANNING, INC.
d/b/a STORE DESIGN & CONSTRUCTION
Three Limited Parkway · Columbus, Ohio 43230
Telephone: 614.415.7000 · Fax: 614.415.7349

PROJECT INFORMATION:

010501726

PINK VICTORIA'S SECRET
FAYETTE MALL
3401 NICHOLASVILLE RD
SPACE # I-904
LEXINGTON, KY 40503

SCOPE: NEW | PACKAGE: A
DESIGN TYPE: PINK | GENERATION: 151Sa
LSD&C PROJECT #: 00062007 | A/E PROJECT #: 20140534

REVISIONS:

REQUIRED BY: DATE

ELITE CONSTRUCTION GROUP
LAKE JACKSON, TX
PHONE: 979-285-0712
NOTE: THESE PRINTS HAVE BEEN REDUCED BY 50 PERCENT. SCALE WILL BE 50 PERCENT OF WHAT IS NOTED ON PLANS

DATE ISSUED: 09-05-2014
DESIGNED BY: APL
DRAWN BY: ANW
CHECKED BY: AJD

RESPONSIBILITY SCHEDULE

DRAWING NUMBER:
A00.01