

ABBREVIATIONS, RESPONSIBILITY SCHEDULES			
FPC	FIRE PROTECTION CONTRACTOR	LD	LIGHTING PACKAGE DISTRIBUTOR
AHJ	AUTHORITY HAVING JURISDICTION	LL	LANDLORD
GC	GENERAL CONTRACTOR	LS&C	LIMITED STORE DESIGN & CONSTRUCTION
LC	LANDLORD CONTRACTOR	MC	MECHANICAL CONTRACTOR

ABBREVIATIONS - PLUMBING					
AD	ACCESS DOOR	G	GAS	PM	PROJECT MANAGER
ADF	AMERICAN DISABILITY ACT	GAL	GALLONS	POC	POINT OF CONNECTION
APA	ABOVE FINISHED FLOOR	GC	GENERAL CONTRACTOR	PRV	PRESSURE REDUCING VALVE
AP	ACCESS PANEL	GPM	GALLONS PER MINUTE	PSI	POUNDS PER SQUARE INCH
CD	CEILING DIFFUSER OR CONDENSATE DRAIN	HB	HOSE BIBB	(R)	RELOCATE
CFM	CUBIC FEET PER MINUTE	HP	HORSEPOWER	RD	REDUCE DRAIN
CI	CAST IRON	HW	HOT WATER	RPBP	REDUCED PRESSURE BACKFLOW PREVENTER
CO	CLEANOUT			RPM	REVOLUTION PER MINUTE
CONT	CONTINUE	INV	INVERT	SCH	SCHEDULE
CONTR	CONTRACTOR	LAV	LAVATORY	SOV	SHUT-OFF VALVE OR SCHEDULE OF VALVE
CTGT	CLEANOUT TO GRADE	LB	POUND		
CW	COLD WATER	LF	LINEAL FEET	UH	UNIT WATER
DET	DETAIL			UN	UNLESS OTHERWISE NOTED
DF	DRINKING FOUNTAIN	MECH	MECHANICAL	UTR	UP THRU ROOF
DL	DOOR LOUVER	MFR	MANUFACTURER		
DS	DREAMSTAMER	MTR	MOUNTED	VTR	VENT THRU ROOF
DTR	DOWN THRU ROOF	MTS	MOTOR		
DWG	DRAWING			WC	WATER CLOSET
(E)	EXISTING	(N)	NEW	WCO	WALL CLEANOUT
EW	ELECTRIC WATER COOLER	N.C.	NORMALLY CLOSED	WG	WATER GAUGE
FCU	FLOOR CLEANOUT	N.I.C.	NOT IN CONTRACT	WH	WATER HEATER
FCU	FAN COIL UNIT	N.O.	NORMALLY OPEN	WH	WATER HAMMER ARRESTER
FD	FLOOR DRAIN	N/A	NOT APPLICABLE	WT	WEIGHT
FDC	FURNISHED BY OWNER, INSTALLED BY CONTRACTOR	NTS	NOT TO SCALE		
FFC	FIRE PROTECTION CONTRACTOR	P	PUMP		
PPS	FEET PER SECOND	PL	PLUMBING CONTRACTOR		
FCS	FLOOR SINK	PD	PRESSURE DROP		
		PLBG	PLUMBING		

THIS SET IS PART OF THE CONSTRUCTION DOCUMENTS, OTHER SHEETS INCLUDING PLANS, DETAILS AND SPECIFICATIONS APPLY. THAT SHOWN HEREON IS SCHEMATIC IN NATURE AND NOT TO BE USED AS A SHOP DRAWING; THEREFORE, INCLUDE ALL MODIFICATIONS REQUIRED TO CONFORM TO THE PROJECT CONDITIONS AND REQUIREMENTS. THE PROJECT LOCATIONS AND DIMENSIONS OF ALL ARCHITECTURAL AND STRUCTURAL ELEMENTS AS SHOWN ON THEIR RESPECTIVE DOCUMENTS, THESE ELEMENTS ARE SHOWN FOR REFERENCE AND SHALL BE VERIFIED PRIOR TO CONSTRUCTION AND SHALL BE THE RESPONSIBILITY OF THE USER. THE ACCURACY OF THESE ELEMENTS, NO DESIGN RESPONSIBILITY IS ASSUMED FOR ANY PORTION OF THE WORK THAT THE PROFESSIONAL ENGINEER HAS NOT SIGNED AND SEALED PER STATE OR PROVINCE REQUIREMENTS.

PLUMBING FIXTURE SCHEDULE-BBW	NIS	E 11/18/13
	42N-P0101-E00-SCHD	

NEITHER UNLESS OTHERWISE SPECIFIED, CONTRACTOR SHALL PROVIDE ALL NECESSARY EQUIPMENT, MATERIAL, LABOR AND SUPERVISION NECESSARY TO COMPLETE THE PLUMBING WORK IN ACCORDANCE WITH THE SPECIFICATIONS AND STANDARDS.

FIELD VERIFY EXACT SIZE AND LOCATION OF EXISTING WASTE PIPING BELOW SLAB, VENT PIPING ABOVE CEILING AND UP THROUGH ROOF AND COLD WATER SUPPLY PIPING ABOVE CEILING PRIOR TO COMMENCEMENT OF ANY WORK, AFTER INSTALLATION AND FINAL CONNECTION OF NEW WASTE PIPING BELOW SLAB, BACKLASH AND PATCH IN ACCORDANCE WITH THE LANDLORD'S CRITERIA REGARDING SUCH WORK.

CONTRACTOR SHALL FURNISH AND INSTALL ALL OF THE NECESSARY PLUMBING FIXTURES (SEE PLUMBING RESPONSIBILITY SCHEDULE ON THIS SHEET) PIPING, ELBOWS, TEES, BACKLASH AND PATCH IN ACCORDANCE WITH THE LANDLORD'S CRITERIA REGARDING SUCH WORK. CONTRACTOR SHALL DEMISED PREMISE TO CONNECTION PROVIDED BY LANDLORD.

SANITARY VENTS SHALL BE ROUTED TO THE EXISTING LANDLORD'S POINT OF CONNECTION WITH THE TENANT'S DEMISED PREMISES OR TO A POINT APPROVED BY LOCAL AUTHORITY. THE CONTRACTOR SHALL PROVIDE A CAPPED TEE FOR POSSIBLE FUTURE CONNECTION (IF REQUIRED BY THE LANDLORD). CONTRACTOR SHALL COORDINATE ALL ROOF PENETRATIONS WITH THE LANDLORD'S ROOFING CONTRACTOR, AS REQUIRED. VENT THRU ROOF SHALL BE AT LEAST 15 FEET AWAY FROM A/C UNIT FRESH AIR INTAKE.

SEAL AROUND ALL PIPES PENETRATING FIRE SEPARATIONS WITH LISTED AND APPROVED FIRE SEAL MATERIAL. ONLY LISTED AND APPROVED SEALANTS AND METHODS FOR THE SPECIFIC USE WILL BE PERMITTED.

THE CONTRACTOR SHALL INSTALL ALL TOILET FIXTURES IN ACCORDANCE WITH ALL CODES AND AS REQUIRED BY LANDLORD'S CRITERIA. CONTROLS FOR FLUSH VALVES SHALL BE MOUNTED ON THE WIDE SIDE OF THE WATER CLOSET AND NO MORE THAN 44" A.F.F.

THE CONTRACTOR SHALL ENSURE THAT ALL SLAB PENETRATIONS WITHIN THE TENANT'S DEMISED PREMISES ARE PROPERLY SEALED AND REMAIN WATERIGHT TO PREVENT ANY POSSIBLE DAMAGE TO OTHER TENANTS AND/OR TO THE BUILDING. FAILURE TO DO SO SHALL BE AT THE RISK AND SOLE EXPENSE OF THE CONTRACTOR.

ALL MATERIAL SHALL BE NEW AND OF COMMERCIAL GRADE, AND BEAR UNDERWRITER'S LABORATORIES AND UNION LABELS WHERE SUCH LABELING APPLIES.

PLUMBING CONTRACTOR TO FIELD VERIFY PROPER SLOPE OF EXISTING SEWER TO MAIN SEWER PRIOR TO ANY NEW PLUMBING INSTALLATION.

PLUMBING CONTRACTOR MUST VISIT THE JOBSITE TO BECOME FAMILIAR WITH MAJOR ITEMS SUCH AS STRUCTURAL ELEMENTS AND OTHER EXISTING JOB CONDITIONS THAT MAY AFFECT THE WORK. ADDITIONALLY, PLUMBING CONTRACTOR SHALL VERIFY EXACT LOCATIONS AND DIMENSIONS OF SUCH ITEMS AS WASTE, VENTS, WATER LINES, ETC.

PLUMBING CONTRACTOR TO FAMILIARIZE AND FOLLOW SPECIFICATIONS AND DETAILS CONTAINED IN DESIGN CRITERIA OF TENANT HANDBOOK.

PLUMBING CONTRACTOR TO CLEAR ALL EXISTING AND NEW DRAIN LINES AND FIXTURES, PRIOR TO TURNING OVER SPACE TO TENANT.

PLUMBING CONTRACTOR SHALL PROVIDE ACCESS TO VALVES, TRAP PRIMERS, ETC. INSTALLED BEHIND WALLS, FLOORS OR CEILINGS.

NO PVC PLASTIC PIPING ALLOWED WITHIN CEILING VOIDS USED FOR NON-DUCTED RETURN AIR PLENUM OR IN WALLS, EXCEPT IN CANADA WHERE XFR-PVC MAY BE USED IF PERMITTED BY THE AUTHORITY HAVING JURISDICTION.

THE GENERAL CONTRACTOR SHALL FIRE SPRINKLER SUB-CONTRACTOR SHALL DESIGN AND INSTALL FIRE SPRINKLER SYSTEM CONFORMING TO LANDLORD'S CRITERIA, TENANT'S REQUIREMENTS, AND PER LOCAL CODES AND NFPA STANDARDS.

SUBMIT COPY OF FIRE PROTECTION SHOP DRAWINGS BEARING THE FIRE MARSHALL'S APPROVAL TO LANDLORD'S FIELD REP PRIOR TO START OF WORK.

ALL SPRINKLER HEADS MUST BE QUICK RESPONSE TYPE.

<b>PLUMBING CONSTRUCTION NOTES</b>	<b>NIS</b>	<b>A</b>
	00N-P0101-A00-NOTE	09/03/13

[illegible]

**PROJECT INFORMATION:**

**BATH & BODY WORKS**

**WHITE BARN CANDLE CO.**

**THE GARDENS MALL**

3101 PGA BOULEVARD  
PALM BEACH GARDENS, FL 33410

**014200814**

1-14200814

141500814

14200814

**REVISIONS:**

#	OWNER & LANDSCAPE COMMENTS	DATE
1	L.L. COMMENT - MECHANICAL REQUIREMENTS	1/16/2011

**PACKAGES:**  
EASTON-C

**GENERATIONS:**  
4/2/ PROJECT #:

**SCOPE:**  
DESIGN TYPE:  
USING PROJECT #:

**ELITE CONSTRUCTION GROUP**  
LAKE JACKSON, TX  
PHONE: 979-285-0712

**NOTE:** THESE PRINTS HAVE BEEN  
REDUCED 14% - 50 PERCENT SCALE  
WILL BE 50 PERCENT OF WHAT IS  
NOTED ON PLANS

**DATE ISSUED:**

**DESIGNED BY:**

**DRAWN BY:**

**CHECKED BY:**

10/24/2011

JES

JES

NR

**PLUMBING**

**NOTES AND**

**SCHEDULES**

**DRAWING NUMBER:**

**P01.01**

**1-14200814**

141500814

14200814