PLUMBING & FIRE PROTECTION RESPONSIBILITY SCHEDULE

ITEM	FURNISHED BY: LSD&C VENDOR	FURNISHED BY: LANDLORD	INSTALLED BY: CONTR.	INSTALLED BY: LANDLORD	INSTALLED BY: CONTR.	INSTALLED BY: OTHER	RE-USE EXISTING	N/A	REMARKS
PLUMBING FIXTURES & TRIM			GC		GC				UNLESS OTHERWISE NOTED
DRINKING FOUNTAIN AND ASSOCIATED ACCESSORIES.	LD				GC				
SEWER AND VENT PIPING			GC		GC				
TANK WATER HEATER							●		
DOMESTIC HOT AND COLD WATER PIPING			GC		GC				
CONDENSATE DRAIN PIPING							●		
SECOND CONDENSATE DRAIN PIPING								●	
CONDENSATE DRAIN PUMP								●	
GAS PIPING								●	
FLOOR DRAINS, CLEANOUTS, WATER HAMMER ARRESTORS, ETC.			GC		GC				
INSTANTANEOUS WATER HEATER	LD				GC				
DREAMSTEAMER	LD				GC				FOR VS STORES ONLY
DREAMSTEAMER DRAIN PIPING			GC		GC				FOR VS STORES ONLY
SPRINKLER PIPING			FPC		FPC				
SPRINKLER HEADS			FPC		FPC				
FIRE EXTINGUISHERS			FPC		FPC				
AS-BUILTS DRAWINGS			GC						

ABBREVIATIONS, RESPONSIBILITY SCHEDULES

FPC	FIRE PROTECTION CONTRACTOR	LD	LIGHTING PACKAGE DISTRIBUTOR
AHJ	AUTHORITY HAVING JURISDICTION	LL	LANDLORD
GC	GENERAL CONTRACTOR	LSD&C	LIMITED STORE DESIGN & CONSTRUCTION
LC	LANDLORD CONTRACTOR	MC	MECHANICAL CONTRACTOR

RESPONSIBILITY SCHEDULE-VS/PINK

NTS | 05N-P0101-L00-SCHD | L | 09/13/13

ABBREVIATIONS - PLUMBING

AD	ACCESS DOOR	G	GAS	PM	PROJECT MANAGER
ADA	AMERICAN DISABILITY ACT	GAL	GALLONS	POC	POINT OF CONNECTION
AFF	ABOVE FINISHED FLOOR	GC	GENERAL CONTRACTOR	PRV	PRESSURE REDUCING VALVE
AP	ACCESS PANEL	GPM	GALLONS PER MINUTE	PSI	POUNDS PER SQUARE INCH
CD	CEILING DIFFUSER OR CONDENSATE DRAIN	HB	HOSE BIBB	(R)	RELOCATE
CFM	CUBIC FEET PER MINUTE	HD	HEAD	RD	ROOF DRAIN
CI	CAST IRON	HP	HORSEPOWER	RPBP	REDUCED PRESSURE BACKFLOW PREVENTER
CO	CLEANOUT	HW	HOT WATER	RPM	REVOLUTION PER MINUTE
CONT	CONTINUE	INV	INVERT		
CONTR	CONTRACTOR			SCH	SCHEDULE
COTG	CLEANOUT TO GRADE	LAV	LAVATORY	SOV	SHUT-OFF VALVE OR SCHEDULE OF VALVE
CW	COLD WATER	LB	POUND		
		LF	LINEAL FEET		
DET	DETAIL			UH	UNIT HEATER
DF	DRINKING FOUNTAIN	MECH	MECHANICAL	UON	UNLESS OTHERWISE NOTED
DL	DOOR LOUVER	MFR	MANUFACTURER	UTR	UP THRU ROOF
DS	DREAMSTEAMER	MTD	MOUNTED		
DTR	DOWN THRU ROOF	MTR	MOTOR	VTR	VENT THRU ROOF
DWG	DRAWING				
				WC	WATER CLOSET
(E)	EXISTING	(N)	NEW	WCO	WALL CLEANOUT
EWC	ELECTRIC WATER COOLER	N.C.	NORMALLY CLOSED	WG	WATER GAUGE
		N.I.C.	NOT IN CONTRACT	WH	WATER HEATER
FCO	FLOOR CLEANOUT	N.O.	NORMALLY OPEN	WHA	WATER HAMMER ARRESTER
FCU	FAN COIL UNIT	N/A	NOT APPLICABLE	WT	WEIGHT
FD	FLOOR DRAIN	NTS	NOT TO SCALE		
FOIC	FURNISHED BY OWNER, INSTALLED BY CONTRACTOR	P	PUMP		
FPC	FIRE PROTECTION CONTRACTOR	PC	PLUMBING CONTRACTOR		
FPS	FEET PER SECOND	PD	PRESSURE DROP		
FS	FLOOR SINK	PLBG	PLUMBING		

PLUMBING ABBREVIATIONS

NTS | 00N-P0101-J00-ABBR | J | 09/06/13

PLUMBING FIXTURE SCHEDULE-VS/PINK

ITEM	FIXTURE	ROUGH-IN SERVICES: CW	HW	W	V	IW	GAS	DESCRIPTION	REMARKS
WC-1	WATER CLOSET, TANK TYPE	½"	–	4"	2"	–	–	KOHLER "HIGH HO" PRESSURE LITE" MODEL NO. K-3819-T, 1.1 GPF, PRESSURE ASSISTED, WHITE WATER CLOSET WITH ELONGATED "UPRIGHT" ENDING BOWL, "ON SWITCH" MODEL #5361-T-0, 1.1/0.8 GPF, WITH HIGH PERFORMANCE FLUSHSYSTEM TECHNOLOGY, 17" HIGH, WHITE OPEN FRONT SEAT AND COVER, BK-4520, FORMED WITH BOLT CAPS AND CHROME SUPPLY STOP FOR PUBLIC AND NON-PUBLIC RESTROOMS, FLUSH LEVER SHALL BE LOCATED ON THE WIDE SIDE OF THE TOILET.	ACCESSIBLE TYPE
WC-2	WATER CLOSET, (WALL MOUNTED W/ IN-WALL TANK	½"	–	4"	2"	–	–	TOTO #CW748EMFG#2 WALL TANK SYSTEM WITH "MARIS" BOWL #CW748EMG, PROVIDE SD10-SDS34281-COTTON WHITE TOILET SEAT AND TOTO #TET2U#CP POLISHED CHROME BOSS PLATE.	ACCESSIBLE TYPE
LAV-1	LAVATORY (UNDERCOUNTER) FOR V.S. POWDER ROOM	½"	½"	2"	1½"	–	–	JOHNSON TABLE TOP WITH PRE-DRILLED UNDER-COUNTER LAVATORY BY KOHLER CO. TO PROVIDE DEALER SUS-315 CHROME-PLATED, SOLID BRASS HANDLE-FREE FAUCET WITH DRAIN STOPPER/DRAIN AND PRE-PACK HARDWARE BELOW. FURNISH WITH BRUSHED NICKEL SUPPLY STOPS AND P-TRAP, INSULATE P-TRAP AND SUPPLY LINES WITH 3/8" ARMSTRONG "ARMAFLEX" PIPING INSULATION OR EQUIVALENT.	ACCESSIBLE TYPE
LAV-2	LAVATORY (ASSOCIATE AMENITY ROOM)	½"	½"	2"	1½"	–	–	KOHLER K-2053-P "RONIC 20" x 18" WALL HUNG SINK. FURNISH WITH CONCEALED ARM WALL HANGER, CHROME SUPPLY STOPS AND P-TRAP, CHROME FAUCET #K-12414-4-CP WITH DRAIN STOPPER/DRAIN AND OS-CP#4 AERATOR. INSULATE P-TRAP AND SUPPLY LINES WITH 3/8" ARMSTRONG "ARMAFLEX" PIPING INSULATION OR EQUIVALENT. MOUNT AT HEIGHT DIRECTED BY THE ARCHITECT.	ACCESSIBLE TYPE
LAV-3	LAVATORY (DROP-IN, PINK POWDER ROOM)	½"	½"	2"	1½"	–	–	KOHLER "INFADUO" #K-2292-4 LAVATORY IN WHITE. DO TO PROVIDE KOHLER "REVIVE" #K-12417-4-BN BRUSHED NICKEL FINISH MONOMETRIC LAVATORY FAUCET WITH LOW-LEAD COMPLIANCE, 1.5 GPM LOCK HOT TO DO TO PROVIDE GRID DRAIN & TAILPIECE #7129-4-BN. FURNISH WITH BRUSHED NICKEL SUPPLY STOPS AND P-TRAP. INSULATE P-TRAP AND SUPPLY LINES WITH 3/8" ARMSTRONG "ARMAFLEX" PIPING INSULATION OR EQUIVALENT.	ACCESSIBLE TYPE
LAV-4	LAVATORY (UNDERCOUNTER) FOR V.S. POWDER ROOM	½"	½"	2"	1½"	–	–	D.O. SUPPLIER: WATERWORKS SHOWROOM, ITEM#11-58532-S1CP2S, NICKEL FINISH BASIN AND WATERWORKS #STORD-RET#3MJS780, ITEM#07-78771-4009-NI, NICKEL FINISH FAUCET. DO TO PROVIDE GRID STRAINER DRAIN AND OVERFLOW PIPE EXTENSION TO BE ORIENTED TO THE SIDE TO MAINTAIN ACCESSIBLE KNEE CLEARANCE. FURNISH WITH BRUSHED NICKEL SUPPLY STOPS AND P-TRAP. INSULATE P-TRAP AND SUPPLY LINES WITH 3/8" ARMSTRONG "ARMAFLEX" PIPING INSULATION OR EQUIVALENT.	ACCESSIBLE TYPE
LAV-5	LAVATORY (OPTION #1)	½"	½"	2"	1½"	–	–	SINK: AMERICAN STANDARD, STUDIO ABOVE COUNTER RECTANGULAR #0231.001, 17"x13"x4.5", COLOR: WHITE. FURNISH WITH CHROME SUPPLY STOPS, P-TRAP AND WASTE DRAIN, FAUCET: AMERICAN STANDARD #7385.100.002, SERIES: ARCHITECT, #8059.165, AC WASHERED (INCLUDES UL-APPROVED WASH-WIRED AC TRANSFORMER), 2.5 GPM AERATOR, POLISHED CHROME.	ACCESSIBLE TYPE
DF-1	DRINKING FOUNTAIN	½"	–	2"	1½"	–	–	HALSEY TAYLOR SELF-CONTAINED, BARRIER-FREE, ELECTRIC, REFRIGERATED, WALL-MOUNTED, BI-LEVEL WATER COOLER WITH GLASS FILLER KIT #HTVBBL-Q-9685CA. FURNISHED WITH PLUG-IN, 3-WIRE GROUNDING TYPE SERVICE CORD. STANDARD 120V, 60 HZ, 1PH. 120V RECEPTACLE REQUIRED, RATED AT 15 AMP MINIMUM, TO RECEIVE 3-WIRE PARALLEL BLADE GROUNDING TYPE MALE PLUG. PROVIDE CHROME SUPPLY STOP AND P-TRAP. SEE MANUFACTURER'S INSTRUCTIONS FOR PROPER INSTALLATION PER ACCESSIBILITY REQUIREMENTS. GLASS FILLER IS TO BE INSTALLED ON THE HIGH FOUNTAIN.	ACCESSIBLE TYPE
DF-2	DRINKING FOUNTAIN (NON-CHILLED)	½"	–	2"	1½"	–	–	HALSEY TAYLOR 4000-SERIES SELF-CONTAINED, BARRIER-FREE, WALL-MOUNTED, BI-LEVEL WATER COOLER WITH APRON MOUNTING PLATE. PROVIDE CHROME SUPPLY STOP AND P-TRAP. SEE MANUFACTURER'S INSTRUCTIONS FOR PROPER INSTALLATION PER ACCESSIBILITY REQUIREMENTS. DO NOT INSTALL WITH FREEZE RESISTANT BOOSTER.	
MOP	MOP SINK	½"	½"	3"	1½"	–	–	FAIX MOP MOLDED STONE SERVICE BASIN MODEL NO. MSB-2424 WITH VINYL BUMPERGUARD. FURNISH WITH AMERICAN STANDARD FAUCET MODEL NO. 8346.112 WITH INTEGRAL VACUUM BREAKER AND STOPS. PROVIDE 42" RUBBER HOSE WITH FAUCET.	
WH-1	WATER HEATER INSTANTANEOUS	½"	½"	–	–	–	–	CHRONOMITE INSTANT-FLOW #M-20L, 0.5 GPM @ 57° RISE, 4160 WATTS, 20 AMP BREAKER, 208V-1#-60.	INSTALL BELOW SINK
WH-2	WATER HEATER TANK TYPE	¾"	¾"	–	–	½"	–	RHEEM WATER HEATER MODEL NO. RESP-6-2.5 (6 GALLON 208V-1#-DR, 2.5 KW AND 14.4 AMPS	
TP	TRAP PRIMER	½"	–	–	–	–	–	PRECISION PLUMBING PRODUCTS TRAP PRIMER, MODEL NO. P-2, COPPER BODY, ADJUSTABLE WITH ½" COPPER TYPE "L" TO FLOOR DRAIN.	
FD	FLOOR DRAIN	–	–	2"	1½"	–	–	ZURN FLOOR DRAIN MODEL NO. Z-415-6B, CAST IRON BODY, COMBINATION INVERTIBLE CLAMP AND ADJUSTABLE COLLAR, 2" BOTTOM OUTLET WITH 6" ROUND NICKEL BRONZE STRAINER.	WITH DEEP SEAL P-TRAP
WHA	WATER HAMMER ARRESTER	–	–	–	–	–	–	SIOUX CHIEF 650 SERIES WATER HAMMER ARRESTER OR EQUAL. *SIZE & INSTALL PER PDI #WH-201 STANDARD OR MANUFACTURER'S INSTRUCTION.	*
WCO	WALL CLEANOUT	–	–	–	–	–	–	ZURN ZN-1446-BP CLEANOUT TEE, DURA-COATED CAST IRON BODY, GAS AND WATER TIGHT BRONZE PLUG AND STAINLESS STEEL WALL ACCESS COVER WITH SECURING SCREW.	
FCO	FLOOR CLEANOUT	–	–	–	–	–	–	ZURN FLOOR CLEANOUT MODEL NO. ZN-1400 WITH GAS-TIGHT AND WATER-TIGHT TAPERED THREADED PLUG AND ROUND POLISHED NICKEL BRONZE SCORIATED ADJUSTABLE TOP.	
CO	CLEANOUT	–	–	–	–	–	–	ZURN CLEANOUT FERRULE WITH PLUG #Z1440 WITH DURA-COATED CAST IRON BODY, WITH GAS-TIGHT AND WATER-TIGHT ABS TAPERED THREADED PLUG.	
SK	BREAK SINK	½"	½"	2"	1½"	–	–	DAYTON D11719 SINGLE BOWL SINK (19" x 17" x 6⅝" BOWL) WITH CHICAGO 350-VPPABCP MECHANICAL GOOSENECK FAUCET.	ACCESSIBLE TYPE
CP	CONDENSATE PUMP							LITTLE GIANT AUTOMATIC CONDENSATE REMOVAL PUMP, #VCMA-20ULS, ¼ HP, 115V, 1PH/1PH @ 20' HEAD.	
UR	URINAL, WALL MOUNTED	¾"	–	2"	1¼"	–	–	KOHLER "DAMON SURFORM" URINAL MODEL NO. K-4986-ET PUMPUSH WITH KOHLER K-15886 0.5 GPF TOUCH VALVE (OR ZURN #Z6736, 0.125 GPF, WHITE VITREOUS CHINA, WITH ZCHOICE3™ FLUSHOMETER VALVE)	U.S. GPF MAXIMUM ACCESSIBLE TYPE
DP	DRAIN PUMP BASIN			1½" (N.C.) 1½" (N.O.)				ZOELLER #133, FLOOR MOUNTED 5.5 GAL. POLYETHYLENE BASIN WITH GASKETED POLYETHYLENE LID. PUMP: ZOELLER #M98, 115V-1Ø, ½ HP, 4725 RPM, 55 GPM @ 10' HD. INCLUDES POWER PASSEE, 4' SWITCH CORD, ELECTRICAL CONNECTION TO BE MADE WITH 14 FT. OIL UNITED 3 WIRE CORD AND PLUG. BASIN AND PUMP TO BE TEMPERATURE RATED TO 180°F. 2" PVC DISCHARGE WITH CHECK VALVE, MODEL #10-0282-115V-1PT NORMALLY OPEN (N.O.) SINGLE PROPYLBLOK FLOAT SWITCH, MODEL #10-0964-115V-15FT NORMALLY CLOSED (N.C.) SINGLE PROPYLBLOK FLOAT SWITCH.	
TMV	THERMOSTATIC MIXING VALVE							SYMMONS MIXING VALVE #7-352-CK "MASTER" 4" INLETS AND OUTLET THERMOSTATIC CONTROLLED MIXER UNDERSINK SERIES, ON SINGLE BOWL WITH 304L STAINLESS STEEL STRAINER, MANUAL-RESISTANT TEMPERATURE ADJUSTMENT KNOBS SET TO 120°, MOUNT IN ACCESSIBLE LOCATION TYPICAL UNDER SINK IN LEAST VISIBLE LOCATION POSSIBLE.	

PLUMBING FIXTURE SCHEDULE-VS/PINK

NTS | 05N-P0101-E00-SCHD | E | 04/09/14

NEW WASTE OR SAN. SEWER	FLOOR CLEAN-OUT
EXISTING WASTE OR SAN. SEWER	WALL CLEAN-OUT
CONDENSATE DRAIN	FLOOR DRAIN
GAS	VENT THRU ROOF
NEW VENT	POINT OF CONNECTION
EXISTING VENT	WATER METER
NEW COLD WATER	SHUT-OFF VALVE
EXISTING COLD WATER	CONCEALED SPRINKLER HEAD
NEW HOT WATER	RECESSED PENDANT SPRINKLER HEAD
EXISTING HOT WATER	UPRIGHT SPRINKLER HEAD BRASS FINISH
PIPE DROP	PENDANT SPRINKLER HEAD BRASS FINISH
PIPE RISE	EXISTING SPRINKLER HEAD
	PORTABLE FIRE EXTINGUISHER

FINISH:
CONCEALED AND RECESSED PENDANT HEADS WHITE UNLESS OTHERWISE NOTED
B: BLACK
C: CHROME

LEGEND AND SYMBOLS

NTS | 00N-P0101-D00-LGND | D | 09/03/13

1. THESE PLANS MAY BE USED FOR CONSTRUCTION ONLY AFTER APPROVAL IS OBTAINED FROM THE BUILDING DEPARTMENT PLUMBING PLAN CHECK DIVISION AND THAT DIVISION'S STAMPED APPROVAL AND AUTHORIZED SIGNATURE APPEAR ON THE PLANS.
2. COORDINATE ALL WORK WITH ALL TRADES INCLUDED BUT NOT LIMITED TO ELECTRICAL, FIRE PROTECTION, MECHANICAL AND STRUCTURAL CONTRACTORS. INSTALL ALL WORK TO CLEAR NEW AND EXISTING ARCHITECTURAL AND STRUCTURAL MEMBERS. NO ITEM SUCH AS PIPE, DUCT, ETC. IS TO BE IN CONTACT WITH ANY EQUIPMENT.
3. REFER TO ARCHITECTURAL DRAWINGS FOR DEMOLITION WORK.
4. REFER TO ARCHITECTURAL DRAWINGS FOR EXACT FIXTURE LOCATION.
5. CONTRACTOR SHALL PROVIDE CUT SHEETS TO LSD&C FOR ALL EQUIPMENT AND DEVICES FURNISHED BY THE CONTRACTOR THAT DEVIATE FROM SPECIFIED ITEM FOR REVIEW AND APPROVAL PRIOR TO THE PURCHASE OF ANY SUCH EQUIPMENT OR DEVICES.
6. THE PLUMBING CONTRACTOR SHALL BE RESPONSIBLE TO FIELD VERIFY THE EXACT LOCATIONS, SIZES, INVERTS AND CONDITION OF EXISTING SANITARY WASTE PIPING BELOW SLAB, VENT PIPING ABOVE CEILING AND UP THROUGH ROOF AND DOMESTIC COLD WATER SUPPLY PIPING TO TENANT'S DEMISED PREMISES PRIOR TO SUBMITTING HIS BID. NO ADDITIONAL COMPENSATION WILL BE MADE FOR ANY EXTRAS DUE TO CONTRACTOR'S FAILURE TO VISIT THE JOB SITE AND/OR FAILURE TO PREDETERMINE ALL EXISTING CONDITIONS BEFORE SUBMITTING HIS BID.
7. ACCESS TO ALL COMPONENTS AND EQUIPMENT MUST BE PROVIDED TO MEET CODE AND SERVICE/MAINTENANCE EASE.
8. THE CONTRACTOR SHALL VERIFY WITH LOCAL CODES AS TO THE REQUIREMENT/INSTALLATION OF ANY "WATER SAVING" DEVICES TO THE PLUMBING FIXTURES. (EXAMPLE: TOILET, FAUCETS, ETC.).
9. PLUMBING SYSTEM SHALL BE PRESSURE TESTED AND STERILIZED PER LANDLORD'S CRITERIA AND LOCAL AUTHORITY.
10. UPON COMPLETION OF THE WORK, CONTRACTOR SHALL ENSURE THE PROPER WORKING ORDER OF THE SYSTEM(S) AND MAKE ANY ADJUSTMENTS AS REQUIRED.

PLUMBING GENERAL NOTES

NTS | 00N-P0101-C00-NOTE | C | 09/03/13

1. UNLESS OTHERWISE SPECIFIED, CONTRACTOR SHALL PROVIDE ALL NECESSARY EQUIPMENT, MATERIAL, LABOR AND SUPERVISION NECESSARY TO COMPLETE THE PLUMBING WORK IN ACCORDANCE WITH THE SPECIFICATIONS AND STANDARDS.
2. FIELD VERIFY EXACT SIZE AND LOCATION OF EXISTING WASTE PIPING BELOW SLAB, VENT PIPING ABOVE CEILING AND UP THROUGH ROOF AND COLD WATER SUPPLY PIPING ABOVE CEILING PRIOR TO COMMENCEMENT OF ANY WORK. AFTER INSTALLATION AND FINAL CONNECTION OF NEW WASTE PIPING BELOW SLAB, BACK FILL AND PATCH IN ACCORDANCE WITH THE LANDLORD'S CRITERIA REGARDING SUCH WORK.
3. CONTRACTOR SHALL FURNISH AND INSTALL ALL OF THE NECESSARY PLUMBING FIXTURES (SEE PLUMBING RESPONSIBILITY SCHEDULE ON THIS SHEET) TO SERVE THE TENANT'S DEMISED PREMISES AND MAKE NECESSARY INSTALLATION OF DOMESTIC WATER AND SEWER PIPING FROM TENANT'S DEMISED PREMISE TO CONNECTION PROVIDED BY LANDLORD.
4. SANITARY VENTS SHALL BE ROUTED TO THE EXISTING LANDLORD'S POINT OF CONNECTION WITHIN THE TENANT'S DEMISED PREMISES OR TO A POINT APPROVED BY LOCAL AUTHORITY. THE CONTRACTOR SHALL PROVIDE A CAPPED TEE FOR POSSIBLE FUTURE CONNECTION (IF REQUIRED BY THE LANDLORD). CONTRACTOR SHALL COORDINATE ALL ROOF PENETRATIONS WITH THE LANDLORD'S ROOFING CONTRACTOR, AS REQUIRED. VENT THRU ROOF SHALL BE AT LEAST 15 FEET AWAY FROM A/C UNIT FRESH AIR INTAKE.
5. SEAL AROUND ALL PIPES PENETRATING FIRE SEPARATIONS WITH LISTED AND APPROVED FIRE SEAL MATERIAL. ONLY LISTED AND APPROVED SEALANTS AND METHODS FOR THE SPECIFIC USE WILL BE PERMITTED.
6. THE CONTRACTOR SHALL INSTALL ALL TOILET FIXTURES IN ACCORDANCE WITH ALL CODES AND AS REQUIRED BY LANDLORD'S CRITERIA. CONTROLS FOR FLUSH VALVES SHALL BE MOUNTED ON THE WIDE SIDE OF THE WATER CLOSET AND NO MORE THAN 44" A.F.F.
7. THE CONTRACTOR SHALL ENSURE THAT ALL SLAB PENETRATIONS WITHIN THE TENANT'S DEMISED PREMISES ARE PROPERLY SEALED AND REMAIN WATERTIGHT TO PREVENT ANY POSSIBLE DAMAGE TO OTHER TENANTS AND/OR TO THE BUILDING. FAILURE TO DO SO SHALL BE AT THE RISK AND SOLE EXPENSE OF THE CONTRACTOR.
8. ALL MATERIAL SHALL BE NEW AND OF COMMERCIAL GRADE, AND BEAR UNDERWRITER'S LABORATORIES AND UNION LABELS WHERE SUCH LABELING APPLIES.
9. PLUMBING CONTRACTOR TO FIELD VERIFY PROPER SLOPE OF EXISTING SEWER TO MAIN SEWER PRIOR TO ANY NEW PLUMBING INSTALLATION.
10. PLUMBING CONTRACTOR MUST VISIT THE JOBSITE TO BECOME FAMILIAR WITH MAJOR ITEMS SUCH AS STRUCTURAL ELEMENTS AND OTHER EXISTING JOB CONDITIONS THAT MAY AFFECT THE WORK. ADDITIONALLY, PLUMBING CONTRACTOR SHALL VERIFY EXACT LOCATIONS AND DIMENSIONS OF SUCH ITEMS AS WASTE, VENTS, WATER LINES, ETC.
11. PLUMBING CONTRACTOR TO FAMILIARIZE AND FOLLOW SPECIFICATIONS AND DETAILS CONTAINED IN DESIGN CRITERIA OF TENANT HANDBOOK.
12. PLUMBING CONTRACTOR TO CLEAR ALL EXISTING AND NEW DRAIN LINES AND FIXTURES, PRIOR TO TURNING OVER SPACE TO TENANT.
13. PLUMBING CONTRACTOR SHALL PROVIDE ACCESS TO VALVES, TRAP PRIMERS, ETC. INSTALLED BEHIND WALLS, FLOORS OR CEILINGS.
14. NO PVC PLASTIC PIPING ALLOWED WITHIN CEILING VOIDS USED FOR NON-DUCTED RETURN AIR PLENUM OR IN WALLS, EXCEPT IN CANADA WHERE XFR-PVC MAY BE USED IF PERMITTED BY THE AUTHORITY HAVING JURISDICTION.
15. THE GENERAL CONTRACTOR'S FIRE SPRINKLER SUB-CONTRACTOR SHALL DESIGN AND INSTALL FIRE SPRINKLER SYSTEM CONFORMING TO LANDLORD'S CRITERIA, TENANT'S REQUIREMENTS, AND PER LOCAL CODES AND NFPA STANDARDS.

PLUMBING CONSTRUCTION NOTES

NTS | 00N-P0101-A00-NOTE | A | 09/03/13

Thorson • Baker + Associates
CONSULTING ENGINEERS
3030 West Streetsboro Road (330) 659-6688 Ph.
Richfield, Ohio 44286 (330) 659-6675 Fax

Limited brands
LIMITED STORE PLANNING, INC.
d/b/a STORE DESIGN & CONSTRUCTION
Three Limited Parkway · Columbus, Ohio 43230
Telephone: 614.415.7000 · Fax: 614.415.7349

PROHIBITION OF RELIEF:
THESE DRAWINGS AND SPECIFICATIONS ARE PREPARED FOR USE ON A SPECIFIC SITE, CONSTRUCTED ONCE(ALL) WITH THEIR SIDE SAFE, THEY ARE NOT INTENDED FOR USE ON A DIFFERENT PROJECT OR SITE. THE REPRODUCTION OF THESE DRAWINGS AND SPECIFICATIONS SHALL BE MADE WITHOUT THE WRITTEN PERMISSION OF THOMAS BAKER ASSOCIATES, INC. © COPYRIGHT ACT, 17 U.S.C. §1 AMENDED DECEMBER 1990 PROTECTS THESE DRAWINGS AND SPECIFICATIONS FROM UNAUTHORIZED USE. ANY REPRODUCTION OF THESE DRAWINGS AND SPECIFICATIONS MUST BE RETURNED TO LSDC UPON COMPLETION OF THEIR INTENDED USE, UNLESS OTHERWISE AGREED BY THE LSDC.

THESE DRAWINGS AND SPECIFICATIONS ARE COPYRIGHTED AND SUBJECT TO COPYRIGHT PROTECTION AS AN "ARCHITECTURAL WORK" UNDER SEC. 102 OF THE COPYRIGHT ACT, 17 U.S.C. §1 AMENDED DECEMBER 1990. THESE DRAWINGS AND SPECIFICATIONS CONTAIN UNPUBLISHED MATERIAL WHICH IS PROPRIETARY TO LSDC. ANY USE OR PUBLICATION OF THESE DRAWINGS AND SPECIFICATIONS WHICH INCLUDES WITHOUT LIMITATION, THE OVERALL FORM, ARRANGEMENT AND COMPOSITION OF SPACES AND ELEMENTS OF THE DESIGN, IN ANY FORM, IS STRICTLY LIMITED. ANY USE OR PUBLICATION OF THESE DRAWINGS AND SPECIFICATIONS MAY RESULT IN CESSATION OF CONSTRUCTION, BUILDING SEIZURE, AND/OR MONETARY DAMAGES.

010500485

PROJECT INFORMATION:

VICTORIA'S SECRET
CAROLINA PLACE
11025 CAROLINA PLACE PKWY
SPACE B-14
PINEVILLE, NC 28134

REFRESH | PACKAGE: PKG II
GENERATION: 2013 (R13.5a)/142Fa
A/E PROJECT #: 2007684009
NMA/ANGELS
00059286

SCOPE:
DESIGN TYPE:
LSDAC PROJECT #:

REVISIONS:

REQUIRED BY:	DATE

ELITE CONSTRUCTION GROUP
LAKE JACKSON, TX
PHONE: 979-285-0712
NOTE: ~~THESE PRINTS HAVE BEEN~~ REDUCED BY 50 PERCENT SCALE
WILL ~~BE 50 PERCENT OF WHAT IS~~ NOTED ON PLANS

DATE ISSUED: 9/26/14
DESIGNED BY: MAR
DRAWN BY: TBA
CHECKED BY: JMZ

PLUMBING NOTES AND SCHEDULES

DRAWING NUMBER:
P01.01