STOREFRONT- VSL

ITEM	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
PRE-FINISHED METAL TRIM / DECORATIVE PROFILES	●				●			
PRE-FINISHED BREAK METAL	●				●			
PRE-FINISHED METAL BASE	●				●			
SIGNAGE							●	
PRE-FINISHED METAL MULLIONS							●	
STOREFRONT GLAZING, U.O.N.							●	-
MARKETING GRID							●	
WINDOW LIGHT BOX TOWER (LBTXX)	●				●			G.C. TO ASSEMBLE, SEE ELECTRIC DWGS FOR POWER.
WALL MOUNTED LIGHTBOX (LBWXX)	●				●			G.C. TO ASSEMBLE, SEE ELECTRIC DWGS FOR POWER.
REVEALS AT NEUTRAL PIERS & BULKHEAD							●	-
PORTAL LIGHT BOX	●				●			POWER AND BLOCKING BY G.C.
LAMINATED RIBBON PATTERN GLASS W/ OPACICOAT	●				●			
BLACK CHERRY GLASS W/ OPACICOAT	●				●			
STOREFRONT VITRENES	●				●			
WINDOW VINYLS	●				●			

SALES AREA- VSL/VSB

ITEM	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
BEAUTY SHELF LIGHTING	●				●			
9-NICHE FOCAL	●				●			INSTALL LOOSE FABRIC PANELS
FRAMED GRAPHICS	●				●			
SCRIPT SIGNAGE VINYLS	●			●				
RIBBON WRAPPED VALANCE PANELS AT BRA SALON	●				●			WITH PRE-INSTALLED HARDWARE
RECESSED STANDARD WALL PANELS	●				●			
DECORATIVE LAMPS / CASHWRAP LAMPS	●				●			
DRUM SHADE	●				●			
CRYSTAL KNOBS AT COLUMNS & PILASTERS	●				●			INSTALL W/ VENDOR SUPPLIED HARDWARE

FITTING ROOMS- VSL

ITEM	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
FITTING ROOM MIRROR DECORATIVE FRAME, MOUNTING FRAME, BACK PANEL, AND GLASS	●				●			G.C. TO PROVIDE BLOCKING
FITTING ROOM HOOKS	●				●			G.C. TO PROVIDE BLOCKING
GO BACK NICHE/CLOSET	●				●			
GO BACK RACK	●				●			
FREESTANDING BRA WARDROBER	●				●			G.C. TO SECURE TO WALL.
FITTING ROOM SEATING	●				●			
DRAPERY, TIE-BACK & ROD	●				●			

STOREFRONT - PINK

ITEM	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
MARKETING PIPE RAILS - PIPES AND FITTINGS		●			●			G.C. TO FIELD PAINT
PINK SIGNAGE: PREFINISHED PLANKS AND EDGE TRIM	●				●			ASSEMBLE PER MFG. INSTRUCTIONS
PINK SIGNAGE: BLOCKING AND BACKING		●			●			
PINK SIGNAGE: "PINK" LETTERS	●			●				
WOOD WINDOW MULLIONS	●				●			PRE-PRIMED, PAINTED BY G.C.
AZEK BASE	●				●			
HEX TILE AT PINK STOREFRONT ENTRY	●				●			THINSET AND GROUT BY G.C.
PREFINISHED PINK WOOD PLANK PANEL (W/ DOG)	●				●			ASSEMBLE PER MFG. INSTRUCTIONS
STOREFRONT GLAZING, U.O.N.							●	
WINDOW VINYL LOGO AND BORDER	●			●				
THIN BRICK, MORTAR AND INSTALLATION ACCESSORIES	●				●			SEE STOREFRONT A08.XX SERIES
DECORATIVE PAINT BRICK FINISH	●			●				
ROUND PILASTER TRIM (AND 5" DOG)	●				●			
REVEALS AT NEUTRAL PIERS & BULKHEAD		●			●			
1/4" (MASONITE), 3/8" AND 3/4" HDF PANELS		●			●			
BLIND DOOR MIRROR: LADDER FRAME, PLY BACKER, J-CHANNELS, SUB-FRAME, AND DECORATIVE FRAME	●				●			
BLIND DOOR MIRROR GLASS, MASTIC AND PRIMER		●			●			
WOOD FLOORING AT DISPLAY WINDOW							●	-

SALES AREA - PINK

ITEM	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
BARRISTER CABINET MIRRORED TRANSOM AT FITTING ROOM / ALCOVE TRANSITION	●				●			GLASS COMES PRE-INSTALLED.
BARRISTER CABINETS INCLUDING MIRRORED VALANCE	●				●			GLASS COMES PRE-INSTALLED.
ACCESSORY CABINETS	●				●			PRE-FINISHED
PUCK PANELS	●				●		●	
PINK FOCAL CABINETS	●				●			PRE-FINISHED
NEON SIGNAGE	●			●				
SUPPORT & POWER FOR NEON SIGNAGE		●			●			
BULB LETTER SIGNAGE	●			●				
SUPPORT & POWER FOR BULB LETTER SIGNAGE		●			●			
SCRIPT LETTER SIGNAGE	●			●				
SUPPORT & POWER FOR SCRIPT LETTER SIGNAGE		●			●			
BACKWRAP MIRROR: 3/4" PLYWOOD MIRROR BACKER, PRIMER & MASTIC		●			●			
BACKWRAP MIRROR TILES AND GOLD LEAF FRAME	●				●			
ILLUMINATED BACKWRAP "PINK" LETTERS	●			●				
POWER FOR BACKWRAP LETTERS		●			●			
BACKWRAP CUBBIES	●				●			
LADDER RAIL PIPE AND BRACKETS	●				●			PRE-FINISHED
BRASS HOOKS AND HARNESS HOOKS	●				●			
MARKETING PIPE RAILS - PIPES AND FITTINGS		●			●			G.C. TO FIELD PAINT
DECORATIVE SALES FLOOR MIRROR: INCLUDES GLASS, PLYWOOD BACKER, J-CHANELS, MASTIC, AND Z-CLIPS	●				●			THIS DOES NOT INCLUDE DOOR MIRRORS
VIDEO MONITOR BACKWRAP	●			●				
VIDEO MONITOR BACKWRAP GOLD LEAF FRAME	●				●			
PRE-PRINTED WALLCOVERING GRAPHICS	●				●			
APPLIED VINYL GRAPHICS	●			●				
FIELD PAINTED BOUNDARY STRIPE APPLIED OVER WALLCOVERING @ CASHWRAP AND POWDER ROOM		●			●			APPLY USING OWNER SUPPLIED STENCIL AND INSTRUCTIONS
FIELD PAINTED LOVE PINK TEXT AT PINK 2	●			●				
FIELD PAINTED STENCILS THROUGHOUT SALES AREA	●			●				WHEN APPLIED OVER PAINTED GYP. BD. OR TRIM, G.C. TO APPLY PRIMER BEHIND STENCIL, SEE SPECIFICATIONS 099000

FITTING ROOMS - PINK

ITEM	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
FITTING ROOM SEATING	●				●			
ALL FITTING ROOM TRIM	●				●			
FIT CARD HOLDER	●				●			
PAPER PANTY HOLDER	●				●			
WALLCOVERING GRAPHIC PANELS	●				●			SEE SHEET A07.XX AND J/A10.09
FITTING ROOM MIRROR: LADDER FRAME, PLY BACKER, J-CHANNELS, SUB-FRAME, AND DECORATIVE FRAME	●				●			
FITTING ROOM MIRROR GLASS, MASTIC AND PRIMER		●			●			THIS DOES NOT INCLUDE DOOR TYPE 'A' (PRE-INSTALLED)
BUILT-IN BRA WARDROBER	●				●			PRE-FINISHED
OUTFITTING CENTER	●				●			PRE-FINISHED
GO-BACK CLOSET	●				●			PRE-FINISHED
MIRROR TRANSOM FOR TRANSITION FROM SALES TO FITTING ROOM ALCOVE	●				●			
FITTING ROOM BENCH	●				●			
PINK FITTING ROOM HOOKS	●				●			G.C. TO PROVIDE BLOCKING
FIELD PAINTED BOUNDARY STRIPE / 'PINK' LOGO OVER WALLCOVERING AT FRS, ALCOVE, AND VESTIBULES		●			●			APPLY USING OWNER SUPPLIED STENCIL AND INSTRUCTIONS
FIELD PAINTED FITTING ROOM GRAPHICS OVERLAPPING TRIM - (PKGA)	●			●				
WALLCOVERING FITTING ROOM GRAPHICS CUT-OFF BY TRIM - (PKGB)	●				●			

STOREFRONT- GLOBAL

ITEM	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
EXTERIOR WATERPROOFING AND FLASHING		●			●			
BLADE SIGN (T.B.D.)	●			●				BLOCKING BY G.C.
STOREFRONT AWNINGS	●			●				BLOCKING BY G.C.
STOREFRONT BANNER	●			●				BLOCKING BY G.C.
IN-WALL BATT INSULATION		●			●			
STOREFRONT STRUCTURAL MEMBERS		●			●			SEE STRUCTURAL DRAWINGS
MALL FLOORING AT STOREFRONT							●	SEE FLOOR AND WALL FINISH PLAN
WALK-OFF ENTRY MAT		●			●			SEE SPECIFICATIONS SECTION 124813
CONCRETE SIDEWALK							●	PER LL REQUIREMENTS
CONCRETE SIDEWALK PATCH AND REPAIR		●			●			AS REQUIRED
UV PROTECTION FILM		●			●			REFER TO SPECIFICATIONS SECTION 088100
IMPACT RESISTANT METAL MULLIONS		●			●			FOR USE IN HURRICANE ZONES
TOUCH-UP FINISHES AT STOREFRONT		●			●			REFER TO A08.X

SALES AREA - GLOBAL

ITEM	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
CASHWRAPS, CASHWRAP FILLERS & BACKWRAPS	●				●			FILLER AS REQUIRED
ANTI-FATIGUE MAT AT CASHWRAP	●				●			
CASHWRAP EQUIPMENT, DETAGGERS, AND SIGNATURE CAPTURE.	●			●				
FURNITURE, FIXTURES & PRESENTATION ITEMS	●				●			G.C. TO UNCRATE, ASSEMBLE AND CLEAN
CABINETWORK (PRE-FINISHED) & ACCESSORIES	●				●			
FINS / GABLES	●				●			
WOOD TRIMS	●				●			SEE DETAILS K/A11.1 AND J/A11.1A
FABRICS AND MOUNTING HARDWARE	●				●			
WALL MOUNTED HANGBARS AND BRACKETS	●				●			
INTERIOR SIGNAGE ELEMENTS	●			●				
FLOORING PATCH AND REPAIR		●			●			REPLACE ANY BROKEN OR DAMAGED FLOORING

NON-SALES STOCKROOM

ITEM	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
VCT FLOORING AND RUBBER BASE		●			●			
SURFACE MOUNTED STANDARDS, BRACKETS, LADDER HOOKS, CLIPS, MOUNTING HARDWARE, ETC.	●				●			
HANGROD, BRACKETS, END CAPS, CONNECTORS FOR NON-SALES	●				●			
3/4" WALL MOUNTED WOOD SHELVING		●			●			
FIXED RIVET RACK SHELVING AND HARDWARE	●				●			
MOBILE SHELVING AND HARDWARE	●				●			
MOBILE SHELVING CRANK SYSTEM	●				●			
BRUSHED STAINLESS STEEL CORNER GUARDS		●			●			REFER TO A/A13.1 PURCHASED THROUGH CBC
DRAWING PLAN TUBE		●			●			
MARKETING STORAGE BINS		●			●			
HARDWARE STORAGE BINS		●			●			
PROCESSING WORK STATION	●				●			PROVIDED BY LLS
STORAGE LEDGE SIGNAGE		●			●			

BREAK ROOM

ITEM	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
REFER TO A/A13.1 FOR SPECS AND RESPONSIBILITIES								

TOILET ROOMS

ITEM	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
REFER TO A/A13.1 FOR SPECS AND RESPONSIBILITIES.							●	SMALL ADDED AREA AND SINK RELOCATION ONLY.

OFFICES

ITEM	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
REFER TO A/A13.1 FOR SPECS AND RESPONSIBILITIES								

GENERAL

ITEM	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS
GYPSUM BOARD: CEILINGS, WALLS, ETC. AND REQUIRED FRAMING & BLOCKING		●			●		●	SEE SPECIFICATIONS SECTION 092900 & 092950
CONCEALED IN-WALL WOOD OR METAL BLOCKING FOR ALL ITEMS IN STORE		●			●			F.R.T. AS REQUIRED
PAINT		●			●			
DOORS, FRAMES & HARDWARE								SEE DOOR SCHEDULE A/A00.2
DOOR CHIMES	●				●			
LAY-IN CEILING (TILE & GRID)		●			●		●	SEE SPECIFICATIONS SECTION 095123
FIRE EXTINGUISHERS		●			●		●	SEE SPECIFICATIONS
EXIT & EMERGENCY LIGHTS	●				●			
CEILING AND WALL ACCESS PANELS		●			●		●	SEE SPECIFICATIONS SECTION 083100
FIBERGLASS REINFORCED PANELS (F.R.P.)		●			●			
ALL FURRING		●			●		●	
FLOOR PROTECTION DURING CONSTRUCTION		●			●			1/8" MASONITE
SAW CUTTING / TRENCHING/ CORE DRILLING		●			●			WHERE REQUIRED PER EQUIPMENT SPECIFIED
MUSIC SYSTEM SUPPORT		●			●			
IP CAMERA CABINET SUPPORT		●			●			
SECURITY MONITOR STRUCTURAL SUPPORT		●			●			
SECURITY DOMES	●			●				
ZINC DIVIDER STRIP		●			●			
STUB-UP PRE-WIRING		●			●			
ALL MIRRORS		●			●			UNLESS OTHERWISE NOTED
MIRROR J-CHANNELS AND BACKING		●			●			UNLESS OTHERWISE NOTED
MIRROR MASTIC		●			●			
TILE FLOORING AND WALL FINISHES	●				●			
ALL NATURAL STONE FINISHES	●				●			
GROUT, SEALANT, THINSET, AND MORTAR		●			●			UNLESS OTHERWISE NOTED
DEMISING WALL FRAMING							●	
DEMISING WALL GYP. BD.							●	
FLOOR PREPARATION & LEVELING		●			●			AS REQUIRED
CONCRETE SLAB		●			●			AS REQD, COORDINATE W/ LANDLORD
FIRE PATCHING / FIREPROOFING		●			●			AS REQD BY CODE / TENANT CRITERIA
WALL COVERINGS	●				●			
WOOD FLOORING	●				●			SEE SPECIFICATIONS SECTION 096429
WOOD FLOORING VAPOR BARRIER AND ADHESIVE		●			●			SEE SPECIFICATIONS SECTION 096429
WOOD FLOORING MOISTURE TEST		●			●			SEE SPECIFICATIONS SECTION 096429
EXPANSION JOINT COVERS		●			●			
CURTAIN TRACK, FABRIC, AND TIE-BACK HOOK	●				●			
CARPET	●				●			
CARPET BINDER BAR EDGE STRIPS		●			●			
CARPET SHIELD		●			●			
SOUND ATTENUATION INSULATION		●			●			SEE WALL SCHEDULE
LIGHT FIXTURES AND LAMPS		●			●			REFER TO ELECTRICAL DRAWINGS
LAMPS FOR ALL EXISTING LIGHT FIXTURES		●			●			REFER TO ELECTRICAL DRAWINGS

DEMOLITION

ITEM	FURNISHED BY O	FURNISHED BY G	FURNISHED BY L	INSTALLED BY O	INSTALLED BY G	INSTALLED BY L	E	REMARKS (INCLUDES: BARRICADE AND PHASING)
BARRICADE PANEL (STRUCTURE)		●			●			
BARRICADE GRAPHICS - FULL BLEED (PKG 1, 1+, PINK FREESTANDING)	●			●				REQUIRES L.L. APPROVAL
BARRICADE GRAPHICS - PARTIAL BLEED (PKG II)	●				●			REQUIRES L.L. APPROVAL
PAINT FINISH		●			●			
TEMPORARY POWER SETUP		●			●			
DE-INSTALLATION AND DE-BRANDING		●			●			SEE P/A00.0
BARRICADE REMOVAL					●			
CHAIN LINK FENCE (IF REQUIRED)		●			●			
SURFACE MOUNTED STANDARDS FOR PHASED STORES	●				●			
TEMPORARY PRE-FAB FITTING ROOMS FOR PHASED STORES	●				●			

ELECTRICAL

ELECTRICAL WORK (AS SPECIFIED) — SEE ELECTRICAL DRAWINGS

FIRE ALARM

FIRE ALARM WORK (AS SPECIFIED) — SEE ELECTRICAL DRAWINGS

MECHANICAL

MECHANICAL WORK (AS SPECIFIED) — SEE MECHANICAL DRAWINGS

PLUMBING

PLUMBING WORK (AS SPECIFIED) — SEE PLUMBING / FIRE PROTECTION DRAWINGS

FIRE PROTECTION

FIRE PROTECTION WORK (AS SPECIFIED) — SEE PLUMBING / FIRE PROTECTION DRAWINGS

STRUCTURAL

STRUCTURAL WORK (AS SPECIFIED) — SEE STRUCTURAL DRAWINGS

RESPONSIBILITY SCHEDULE

ANNOTATIONS: O: OWNER (LIMITED BRANDS OR VENDOR) G: GENERAL CONTRACTOR L: LANDLORD E: EXISTING

NO SCALE
-
A

Stantec
Stantec Architecture Inc.
1383 N. McDowell Blvd., Suite 250
Petaluma, CA U.S.A. 94954
Tel. 707.765.1660 Fax. 707.765.9908
www.stantec.com

GARY M. SEMLING
REGISTERED ARCHITECT
12151
9-26-14
NORTH CAROLINA
PETALUMA, CA

Limitedbrands
LIMITED STORE PLANNING, INC.
d/b/a STORE DESIGN & CONSTRUCTION
Three Limited Parkway · Columbus, Ohio 43230
Telephone: 614.415.7000 · Fax: 614.415.7349

PROHIBITION ON REUSE:
THESE DRAWINGS AND SPECIFICATIONS WERE PREPARED FOR USE ON A SPECIFIC SITE CONTEMPORANEOUSLY WITH THEIR ISSUE DATE. THEY ARE NOT INTENDED FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. REUSE OF THESE DRAWINGS AND SPECIFICATIONS, OR ANY REPRODUCTION THEREOF, ON ANOTHER PROJECT IS PROHIBITED AND CONTRARY TO LAW UNLESS EXPRESSLY AUTHORIZED IN WRITING BY LIMITED STORE PLANNING, INC., D/B/A LIMITED STORE DESIGN AND CONSTRUCTION ("LSDC").

THESE DRAWINGS AND SPECIFICATIONS ARE THE PROPERTY OF LSDC AND SHALL NOT BE DISPLAYED IN ANY MANNER OR USED ON ANY OTHER PROJECT EXCEPT BY WRITTEN AGREEMENT WITH LSDC. NO REPRODUCTION OF THESE DRAWINGS AND SPECIFICATIONS SHALL BE MADE WITHOUT THE WRITTEN AUTHORIZATION OF THE LSDC. ALL ORIGINALS OR REPRODUCTIONS OF THESE DRAWINGS AND SPECIFICATIONS MUST BE RETURNED TO LSDC UPON COMPLETION OF THEIR INTENDED USE, UNLESS OTHERWISE AGREED BY THE LSDC.

COPYRIGHT NOTICE:
THESE DRAWINGS AND SPECIFICATIONS ARE COPYRIGHTED AND SUBJECT TO COPYRIGHT PROTECTION AS AN "ARCHITECTURAL WORK" UNDER SEC. 102 OF THE COPYRIGHT ACT, 17 U.S.C. AS AMENDED DECEMBER 1990; KNOWN AS THE ARCHITECTURAL WORKS COPYRIGHT PROTECTION ACT OF 1990. THE PROTECTION INCLUDES, WITHOUT LIMITATION, THE OVERALL FORM, ARRANGEMENT AND COMPOSITION OF SPACES, AND ELEMENTS OF THE DESIGN. UNDER SUCH PROTECTION, UNAUTHORIZED USE OF THESE DRAWINGS AND SPECIFICATIONS MAY RESULT IN CESSATION OF CONSTRUCTION, BUILDING SEIZURE, AND/OR MONETARY LIABILITY.

010500485

PROJECT INFORMATION:
VICTORIA'S SECRET
CAROLINA PLACE
11025 CAROLINA PLACE PKWY
SPACE B-14
PINEVILLE, NC 28134

SCOPE: REFRESH
DESIGN TYPE: NMA/ANGELS
LSD&C PROJECT #: 00059286
PACKAGE: PKG II
GENERATION: R131Sa/142Fa
A/E PROJECT #: 2007684009

REVISIONS:
REQUIRED BY: DATE

ELITE CONSTRUCTION GROUP
LAKE JACKSON, TX
PHONE: 979-285-0712
NOTE: THESE PRINTS HAVE BEEN REDUCED BY 50 PERCENT. SCALE WILL BE 50 PERCENT OF WHAT IS NOTED ON PLANS

DATE ISSUED: 9/26/14
DESIGNED BY: KW
DRAWN BY: DB
CHECKED BY: DB

RESPONSIBILITY SCHEDULE

DRAWING NUMBER:
A00.1