

REGULATIONS

1. THE CONTRACTOR SHALL HAVE EVIDENCE OF CURRENT WORKER'S COMPENSATION INSURANCE ON FILE IN COMPLIANCE WITH LOCAL CODE.

2. BEFORE COMMENCING WITH THE WORK, THE G.C. SHALL SHOW EVIDENCE OF ALL THE INSURANCE REQUIREMENTS.

3. THE CONTRACTOR SHALL BE FAMILIAR WITH ALL LANDLORD REQUIREMENTS AND SHALL BE RESPONSIBLE FOR COMPLIANCE WITH SAME. THE CONTRACTOR SHALL INVESTIGATE LOCAL CODES AND PROCEDURES AND SHALL COMPLY WITH ALL REQUIREMENTS.

4. SIGN CONTRACTOR TO OBTAIN SIGN PERMITS FROM BUILDING DEPARTMENT AS APPLICABLE. AN IDENTIFYING STICKER MAY BE INSTALLED, PROVIDING IT CANNOT BE SEEN BY PASSEGBY.

5. THE CONTRACTOR SHALL MAINTAIN FOR THE ENTIRE DURATION OF THE WORK ALL EXITS, EXIT LIGHTING, FIRE PROTECTION DEVICES AND ALARMS IN CONFORMANCE WITH ALL APPLICABLE CODES AND ORDINANCES.

6. PROVIDE OCCUPANCY SIGNS CONFORMING TO APPLICABLE BUILDING CODE REQUIREMENTS.

7. PROVIDE ADDITIONAL EXIT SIGNS AND FIRE EXTINGUISHERS IN TYPE, NUMBER AND LOCATIONS AS DIRECTED BY THE FIRE DEPARTMENT FIELD INSPECTOR.

JOB SITE OPERATIONS

1. DURING ALL PHASES OF WORK DO NOT DISTURB THE DELIVERIES AND FUNCTIONS OF ADJACENT AND NEIGHBORING TENANTS.

2. EACH CONTRACTOR SHALL LEAVE THE SITE IN A NEAT, CLEAN AND ORDERLY CONDITION UPON THE COMPLETION OF THEIR WORK ON A DAILY BASIS. AREA OF WORK TO BE DUSTED, SWEEPED AND MOPPED TO SATISFACTORY CONDITION AS START OF WORK. ALL WASTE, RUBBISH AND EXCESS MATERIALS SHALL BE REMOVED FROM THE SITE PROMPTLY. THE G.C. SHALL BE RESPONSIBLE FOR REMOVAL AND DISPOSAL OF ALL TRASH, INCLUDING TRASH GENERATED FROM OWNER FURNISHED ITEMS AND BY OWNER'S CONTRACTORS FOR THE DURATION OF THE PROJECT.

3. ALL EXISTING WORK NOT IN THIS SCOPE OF WORK SHALL BE MAINTAINED IN ITS ORIGINAL CONDITION, U.N.O. PROTECT WORK FROM DAMAGE RESULTING FROM THIS WORK.

4. REMOVE ALL ABANDONED IMPROVEMENTS, INCLUDING ELECTRICAL AND MECHANICAL, U.N.O.

MATERIALS

1. WHEN CONTRACTOR ACCEPTS DELIVERY OF ALL ITEMS NOTED ON PLANS WHETHER IN CONTRACT OR NOT IN CONTRACT, THE G.C. SHALL BE RESPONSIBLE FOR LOSS AND/OR DAMAGE TO THESE ITEMS.

2. G.C. SHALL BE RESPONSIBLE FOR COORDINATION WITH OWNER'S REPRESENTATIVE TO PROVIDE A TIMELY ARRIVAL OF ALL MATERIALS, EQUIPMENT AND OTHER SUCH ITEMS TO BE UTILIZED ON THIS PROJECT (OWNER-PROVIDED OR OTHERWISE). G.C. SHALL NOTIFY OWNER'S REPRESENTATIVE IN WRITING WITHIN 5 DAYS OF DATE OF APPROVED WORK AUTHORIZATION OF THOSE ITEMS THAT MAY NOT BE READILY AVAILABLE. IF NOTIFICATION IS NOT PROVIDED TO THE OWNER'S REPRESENTATIVE, THE CONTRACTOR ACCEPTS RESPONSIBILITY FOR THE PROPER ORDERING AND FOLLOW-UP OF SPECIFIED ITEMS AND WILL PURSUE WHATEVER MEANS NECESSARY AT NO ADDITIONAL COST TO OWNER.

3. CONTRACTOR TO ENSURE AVAILABILITY OF ALL SPECIFIED ITEMS SO AS NOT TO CREATE A HARDSHIP TO THE OWNER AND NOT DELAY PROGRESS OF THE WORK. NO EXTENSION OF TIME SHALL BE PERMITTED.

4. CONTRACTOR SHALL BE RESPONSIBLE TO RECEIVE, INVENTORY, STORE AND SECURE ANY OWNER FURNISHED ITEMS (PFI) SUPPLIED AND DELIVERED TO THE JOBSITE, OR OTHER AGREED UPON LOCATION, AND FORWARD THE RECEIVING DOCUMENT(S) TO THE OWNER.

5. THE CONTRACTOR SHALL LEAVE WITH STORE MANAGER ONE (1) GALLON OF PAINT OF EACH COLOR FOR FUTURE TOUCH-UP WORK.

6. NO SUBSTITUTIONS OF ANY MATERIALS OR ITEMS SPECIFIED IN THE DOCUMENTS ARE PERMITTED, U.N.O. AND APPROVED BY OWNER.

7. ANY WOOD CONSTRUCTION SHALL BE FIRE RETARDANT TREATED. INTERIOR FINISHES SHALL NOT EXCEED A FLAME SPREAD RATING OF 25 AT EXIT CORRIDORS.

8. G.C. RESPONSIBLE FOR COORDINATING ALL OWNER PROVIDED VENDORS FOR DELIVERY INCLUDING, RETURN OF ANY EXCESS MATERIALS.

DRAWINGS

1. ALL CONTRACTORS, SUBCONTRACTORS, VENDORS AND MATERIAL SUPPLIERS SHALL BE RESPONSIBLE FOR REVIEWING THE COMPLETE SET OF DOCUMENTS AS SHOWN IN THE SHEET INDEX. FAILURE TO REVIEW CONSTRUCTION DOCUMENTS WILL NOT RELIEVE ANY CONTRACTORS, SUBCONTRACTORS, VENDORS OR MATERIAL SUPPLIERS FROM PERFORMING WORK OR PROVIDING MATERIALS REQUIRED FOR THIS PROJECT AS DEFINED WITHIN THE DOCUMENTS AT TIME OF BID.

2. G.C. SHALL COORDINATE WORK PERFORMED BY OTHER CONTRACTORS. ANY DISCREPANCIES SHALL BE BROUGHT TO THE OWNER'S ATTENTION (VERBALLY & DOCUMENTED IN WRITING) BEFORE PROCEEDING WITH WORK.

3. SHOULD A CONFLICT EXIST BETWEEN THE CONSTRUCTION DOCUMENTS AND/OR THE SPECIFICATIONS THE OWNER'S REPRESENTATIVE SHALL BE INFORMED (VERBALLY & DOCUMENTED IN WRITING) OF THIS DISCREPANCY IMMEDIATELY AT WHICH TIME OWNER'S REPRESENTATIVE SHALL PROVIDE DIRECTION AS TO HOW TO PROCEED.

4. INSPECT SITE AND VERIFY FIELD DIMENSIONS BEFORE COMMENCING WITH CONSTRUCTION. NOTIFY OWNER'S REPRESENTATIVE AND LANDLORD IMMEDIATELY IF THERE ARE ANY DISCREPANCIES.

GENERAL NOTES

DOOR INFORMATION					FRAME INFORMATION				NOTES
MARK	LOCATION	NOMINAL SIZE	MATERIAL	FINISH	MATERIAL	FINISH	FIRE RATING	HEAD/JAMB DETAIL	
101	(E) ENTRY	PR. 3'-0"W. x 7'-0"H.	TEMP. GLASS / ALUM.	EXIST.	ALUM.	EXIST.	-	-	A EXISTING ENTRY DOOR TO REMAIN WITH ALL DOOR HARDWARE. LOCKSET TO BE CLEANED AND RE-GREASED.
102	FITTING ROOM	3'-0"W. x 6'-2"H. x 1 1/2"	WOOD	PRE-FINISHED	ALUM.	PRE-FINISHED	-	-	D PARTITION DOORS & HARDWARE TO BE PROVIDED BY OWNER
103	TOILET ROOM	3'-0"W. x 7'-0"H.	HOLLOW METAL	P-2B SALES/ P-1B NON-SALES	HOLLOW METAL	SALES/P-1B NON-SALES	-	S/A11/ SIM.	C NEW DOOR AND FRAME; EXISTING HARDWARE TO BE REUSED.
104	SALES / NON-SALES	3'-0"W. x 7'-0"H. x 1 3/4"	(E) HOLLOW METAL	P-5A SALES/ P-1B NON-SALES	(E) HOLLOW METAL	SALES/P-1B NON-SALES	-	S/A11/ SIM.	B NO KICKSTANDS ALLOWED; EXISTING TOILET ROOM DOOR TO BE REUSED AT THIS LOCATION. PROVIDE NEW HARDWARE AS SCHEDULED
105	(E) SALES/ NON-SALES	3'-0"W. x 7'-0"H. x 1 3/4"	(E) HOLLOW METAL	P-2B SALES/ P-1B NON-SALES	HOLLOW METAL	SALES/P-1B NON-SALES	-	-	G PROVIDE ANY MISSING OR DAMAGED HARDWARE.
106	(E) SALES/ NON-SALES	3'-0"W. x 7'-0"H. x 1 3/4"	(E) HOLLOW METAL	P-2B SALES/ P-1B NON-SALES	HOLLOW METAL	SALES/P-1B NON-SALES	-	-	G PROVIDE ANY MISSING OR DAMAGED HARDWARE.
107	(E) SERVICE	3'-0"W. x 7'-0"H.	(E) HOLLOW METAL	P-1B	(E) HOLLOW METAL	EXISTING	-	-	F PROVIDE ANY MISSING OR DAMAGED HARDWARE.

A. (E) EXTERIOR ENTRY DOORS - EXISTING DOOR TO REMAIN. G.C. TO CLEAN TO "LIKE NEW" CONDITION. G.C. TO REVIEW HARDWARE WITH CHICO'S PROJECT MANAGER ON SITE. EXISTING HARDWARE TO REMAIN U.N.O. G.C. TO ENSURE PROPER FUNCTION AND REPAIR/REPLACE IN KIND IF REQUIRED.

B. SALES / NON-SALES DOOR: EXISTING TOILET ROOM DOOR TO BE REUSED AT THIS LOCATION. G.C. TO CLEAN TO "LIKE NEW" CONDITION AND PAINT FRAME AND DOOR P-1B. G.C. TO REVIEW HARDWARE WITH CHICO'S PROJECT MANAGER ON SITE. HARDWARE: PUSH PLATE: IVES NO. 8200 3.5" X 15", FINISH 619 PULL: IVES NO. 8302-6 3.5" X 15", FINISH 619 DOOR STOP: ROCKWOOD #445, FINISH 619 SILENCERS: 3 EACH, FINISH 619 HINGES: 1 1/2 PAIR; BOMMER, 4 1/2"x4 1/2", #BB5000 STANDARD WEIGHT, AVERAGE FREQUENCY, FULL MORTISE, BALL BEARING HINGE, FINISH STAINLESS STEEL CLOSER: SARGENT MFG. CO. #143 SERIES, ANSI/BHMA A156.4 GRADE, FINISH 619 (INSTALLED ON NON-SALES SIDE OF DOOR) KICKPLATE: ROCKWOOD K1050, HEAVY DUTY 8"x34", FINISH 619

C. TOILET ROOM DOOR: EXISTING DOOR TO BE REMOVED AND SALVAGED FOR REUSE AS ABOVE. STOCKROOM DOOR: G.C. TO REVIEW HARDWARE WITH CHICO'S PROJECT MANAGER ON SITE. EXISTING TOILET ROOM DOOR HARDWARE TO BE REUSED ON NEW TOILET ROOM DOOR. G.C. TO ENSURE PROPER FUNCTION AND REPAIR/REPLACE IN KIND. UNFINISHED DOOR, FRAME & HARDWARE - SUPPLIED, INSTALLED & FINISHED BY G.C.

D. FITTING ROOM DOOR: FURNISHED DOOR AND HARDWARE SUPPLIED BY OWNER. G.C. TO REVIEW HARDWARE WITH CHICO'S PROJECT MANAGER ON SITE. HARDWARE: HINGES: SCHLAGE F40ELA626, 3.5 X 3.5 SQUARE, SATIN NICKEL HANDLE: SCHLAGE F40ELA626, SATIN CHROME ELAN PRIVACY DOOR LEVER SET

5. DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED DRAWINGS.

6. ARCHITECTURAL DRAWINGS TAKE PRECEDENCE OVER OTHER DRAWINGS FOR LAYOUT DIMENSIONS AND NUMBER OF ITEMS PROVIDED. UPON DISCOVERY OF DISCREPANCIES BETWEEN ARCHITECTURAL DRAWINGS AND ENGINEERING DRAWINGS, OWNER SHALL BE IMMEDIATELY NOTIFIED IN WRITING.

7. IF ANY ERRORS OR OMISSIONS APPEARS IN CONTRACT DOCUMENTS CONTRACTOR SHALL NOTIFY OWNER IN WRITING OF SUCH ERRORS OR OMISSIONS.

8. DIMENSIONS SHOWN ON PLANS ARE TO FACE OF GFIU, CONCRETE COLUMNS OR GRID LINES AND FACE OF GYPSUM BOARD UNLESS OTHERWISE NOTED OR DETAILED. CABINET OPENING DIMENSIONS ARE TO FACE OF FINISH GYP. BD.

9. THE CONTRACTOR SHALL VERIFY ALL DOCUMENTS, VERIFY ALL DIMENSIONS AND FIELD CONDITIONS AND CONFIRM WORK IS BUILDABLE AS SHOWN. ANY CONFLICTS OR OMISSIONS, ETC. SHALL BE IMMEDIATELY REPORTED TO THE ARCHITECT / OWNER FOR CLARIFICATION PRIOR TO PERFORMANCE OF ANY WORK IN QUESTION.

10. COLUMN CENTER LINE (OR GRID LINES) ARE SHOWN FOR DIMENSIONS. VERIFY EXACT LOCATIONS IN FIELD.

11. OWNER'S REPRESENTATIVE AND TENANT ARE THE SAME FOR PURPOSES OF THESE DRAWINGS.

BUILDING ENVELOPE

1. ALL OPENINGS, FLASHINGS, COUNTER FLASHINGS, AND EXPANSION JOINTS SHALL BE WATERTIGHT.

2. ALL OPEN JOINTS, PENETRATIONS AND OTHER OPENINGS IN THE BUILDING ENVELOPE SHALL BE SEALED, CAULKED, GASKETED OR WEATHER-STRIPPED TO LIMIT AIR LEAKAGE.

3. USE ACoustICAL SEALANT AROUND ALL PIPES, DUCTS, CONDUIT, OUTLETS, SWITCHES, ETC. ON BOTH SIDES OF CROSSING / PENETRATING WALLS WITH THERMAL AND ACoustICAL INSULATION.

4. ALL SAW CUTTING AND CORING LOCATIONS SHALL BE REVIEWED AND COORDINATED WITH THE LANDLORD PRIOR TO CUTTING/ CORING.

ANY DISCREPANCIES BETWEEN THE EXISTING CONDITIONS AND THE ACTUAL FIELD CONDITIONS SHALL BE BROUGHT TO THE ATTENTION OF THE OWNER BEFORE PROCEEDING WITH ANY WORK.

GENERAL CONTRACTOR SHALL VISIT THE SITE PRIOR TO SUBMITTAL OF BID TO DETERMINE CONDITIONS AFFECTING THE WORK. ANY ITEMS WHICH ARE NOT COVERED IN THE BID DOCUMENTS OR ANY PROPOSED SUBSTITUTIONS SHALL BE LISTED SEPARATELY AND QUALIFIED IN THE CONTRACTOR'S BID. SUBMITTAL OF BID SHALL SERVE AS EVIDENCE OF KNOWLEDGE OF EXISTING CONDITIONS AND ANY MODIFICATIONS WHICH ARE REQUIRED TO MEET THE INTENT OF THE DRAWINGS AND SPECIFICATIONS. FAILURE TO VISIT THE SITE DOES NOT RELIEVE THE CONTRACTOR OF RESPONSIBILITY IN PERFORMANCE OF WORK.

G.C. TO FIELD VERIFY ALL DIMENSIONS AND SITE CONDITIONS PRIOR TO COMMENCEMENT OF WORK. IF GENERAL CONTRACTOR FINDS ANY DISCREPANCY IN DRAWING SET OR DURING FIELD VERIFICATION THE GENERAL CONTRACTOR IS TO CONTACT OWNER'S REPRESENTATIVE VIA PHONE (OR EMAIL) PRIOR TO COMMENCEMENT OF ANY FURTHER WORK AFTER DISCREPANCY HAS BEEN IDENTIFIED. FAILURE TO DO SO PLACES SOLE RESPONSIBILITY ON THE G.C. FOR ANY WORK DONE REGARDING THAT MATTER.

GENERAL CONTRACTOR SHALL VISIT THE SITE PRIOR TO SUBMITTAL OF BID TO DETERMINE CONDITIONS AFFECTING THE WORK. ANY ITEMS WHICH ARE NOT COVERED IN THE BID DOCUMENTS OR ANY PROPOSED SUBSTITUTIONS SHALL BE LISTED SEPARATELY AND QUALIFIED IN THE CONTRACTOR'S BID. SUBMITTAL OF BID SHALL SERVE AS EVIDENCE OF KNOWLEDGE OF EXISTING CONDITIONS AND ANY MODIFICATIONS WHICH ARE REQUIRED TO MEET THE INTENT OF THE DRAWINGS AND SPECIFICATIONS. FAILURE TO VISIT THE SITE DOES NOT RELIEVE THE CONTRACTOR OF RESPONSIBILITY IN PERFORMANCE OF WORK.

ANY DISCREPANCIES BETWEEN THE EXISTING CONDITIONS AND THE ACTUAL FIELD CONDITIONS SHALL IMMEDIATELY BE BROUGHT TO THE ATTENTION OF THE OWNER AND THE MALL OPERATIONS MANAGER BEFORE PROCEEDING WITH ANY WORK.

G.C. TO FIELD VERIFY ALL DIMENSIONS AND SITE CONDITIONS PRIOR TO COMMENCEMENT OF WORK. IF GENERAL CONTRACTOR FINDS ANY DISCREPANCY IN DRAWING SET OR DURING FIELD VERIFICATION THE GENERAL CONTRACTOR IS TO CONTACT OWNER'S REPRESENTATIVE AND THE MALL OPERATIONS MANAGER VIA PHONE (OR EMAIL) PRIOR TO COMMENCEMENT OF ANY FURTHER WORK AFTER DISCREPANCY HAS BEEN IDENTIFIED. FAILURE TO DO SO PLACES SOLE RESPONSIBILITY ON THE G.C. FOR ANY WORK DONE REGARDING THAT MATTER.

CODE	SUPPLIED	INSTALLED	MATERIAL	MANUFACTURER	DESCRIPTION	LOCATION / NOTES
NOTE: G = GENERAL CONTRACTOR AND O = SO/IA / OWNER						
CEILINGS						
CEG-1	G	G	GYPSUM BOARD	N/A	5/8" SUSPENDED GYPSUM BOARD	SALES FLOOR, LOUNGE AREA, FITTING ROOMS AND HALLWAY/CORRIDOR AS REQUIRED BY CODE
CEG-2	G	G	ACoustICAL TILE	ARMSTRONG	SUSPENSION GRID SYSTEM	GRID: PRELUDE XL EXPOSED TEE 15/16" SYSTEM, 2'X2'X3/4" WHITE TILE; FINE FISURED ANGLED REGULAR (MEDIUM TEXTURE) #717
CEG-3	G	G	ACoustICAL TILE	ARMSTRONG	SUSPENSION GRID SYSTEM	GRID: TYPE 1, PRELUDE XL 15/16" EXPOSED TEE SYSTEM, COLOR: WHITE TILE: CORTESA #717 (#893 FIRE RATED); 24"x36"x1/2" NON-DIRECTIONAL, COLOR: WHITE
CEG-4			ACoustICAL TILE	N/A	2'X2' OR 2'X4' TO REMAIN. REFER TO SHEET A3.1	G.C. TO REPAIR/REPLACE EXISTING TILES & GRID AS REQUIRED TO ACHIEVE "LIKE NEW" CONDITION
CEG-5			GYPSUM BOARD	N/A	EXISTING GYP. BD. CEILING TO REMAIN. REFER TO SHEET A3.1	G.C. TO PATCH/REPAIR AS REQUIRED TO ACHIEVE "LIKE NEW" CONDITION, AS REQUIRED V.I.F.
PAINT						
P-1A	G	G	PAINT	BENJAMIN MOORE	DECORATOR'S WHITE RMI-04	REGAL SELECT WATERBORNE INTERIOR: EGGSHELL
P-1B	G	G	PAINT	BENJAMIN MOORE	DECORATOR'S WHITE RMI-04	REGAL SELECT WATERBORNE INTERIOR - SEMI-GLOSS
P-1C	G	G	PAINT	BENJAMIN MOORE	DECORATOR'S WHITE RMI-04	REGAL SELECT WATERBORNE INTERIOR: FLAT
P-1D	G	G	PAINT	BENJAMIN MOORE	DECORATOR'S WHITE RMI-04	EXTERIOR GRADE - FLAT
P-2A	G	G	PAINT	BENJAMIN MOORE	ELMIRA HC-84	REGAL SELECT WATERBORNE INTERIOR: EGGSHELL
P-2B	G	G	PAINT	BENJAMIN MOORE	ELMIRA HC-84	REGAL SELECT WATERBORNE INTERIOR: SEMI-GLOSS
P-2C	G	G	PAINT	BENJAMIN MOORE	ELMIRA HC-84	EXTERIOR GRADE: EGGSHELL - EIPS FINISH COLOR TO MATCH ELMIRA
P-3A	G	G	PAINT	BENJAMIN MOORE	IGICLE OC-60	REGAL SELECT WATERBORNE INTERIOR - EGG SHELL
P-3B	G	G	PAINT	BENJAMIN MOORE	IGICLE OC-60	REGAL SELECT WATERBORNE INTERIOR: SEMI-GLOSS
P-4A	G	G	PAINT	BENJAMIN MOORE	SPACE BLACK 214-18	EXTERIOR GRADE - EGGSHELL
P-4B	G	G	PAINT	BENJAMIN MOORE	SPACE BLACK 214-18	EXTERIOR GRADE - SEMI-GLOSS
P-5A	G	G	PAINT	BENJAMIN MOORE	TBD	REGAL SELECT WATERBORNE INTERIOR: SEMI-GLOSS
P-6A	G	G	PAINT	BENJAMIN MOORE	PRINCESS PINK TC-28	REGAL SELECT WATERBORNE INTERIOR: SEMI-GLOSS

NO SUBSTITUTIONS ALLOWED. REFER TO SHEET AS.2 FOR PAINTING AND PRIMER SPECIFICATIONS. PROVIDE PREMIUM GRADE PRIMERS RECOMMENDED BY PAINT MANUFACTURER FOR SUBSTRATES INDICATED AND FOR FINISH SYSTEMS SPECIFIED. IF ADDITIONAL INFORMATION IS REQUIRED / NEEDED CONTACT BENJAMIN MOORE ACCOUNT REP PAUL BALLAS AT 201.941.6934

WALL COVERING						
WC-1	O	G	VINYL WALL COVERINGS	KOROSEAL	VENETIAN LINEN CRYSTALLO ORO #821-20	ADHESIVE SUPPLIED BY G.C. AS PER MANUFACTURERS SPECIFICATIONS
WC-2	O	G	TEXTURED VINYL WALL COVERINGS	WALLPAPER DIRECT	SERIES: ANAGLYPTA STYLE: RANNORTH RD03010	G.C. TO PAINT PRINCESS PINK (P-6A)

FLOORING						
FG-1A	G	G	VINYL STRIP	GENTIVA	LINED OAK MP-3304-ENG 5'x16" PRECUT PIECES	SALES & FITTING ROOM LOUNGE - HERRINGBONE PATTERN. INSTALLED BY G.C. AS PER MANUFACTURERS SPECIFICATIONS.
FG-1B	G	G	VINYL STRIP	GENTIVA	LINED OAK MP-3304-ENG 5'x16" STANDARD PIECES	FITTING ROOMS & HINDON THRESHOLDS. INSTALLED BY G.C. AS PER MANUFACTURER'S SPECIFICATIONS. CUT DOWN TO FIT
FG-2A	G	G	HARDWOOD COMPOSITE STRIP	AGI FLOORING	OAK-KU-WFLNL113 3/4"x8" PRECUT PIECES	SALES & FITTING ROOM LOUNGE - HERRINGBONE PATTERN. ADHESIVE SUPPLIED AND INSTALLED BY G.C. AS PER MANUFACTURER'S SPECIFICATIONS.
FG-2B	G	G	HARDWOOD COMPOSITE STRIP	AGI FLOORING	OAK-KU-WFLNL113 7/8"x6" STANDARD PIECES	FITTING ROOMS & HINDON THRESHOLDS. ADHESIVE SUPPLIED AND INSTALLED BY G.C. AS PER MANUFACTURER'S SPECIFICATIONS.
FG-6	G	G	CARPET	MAGLAMB	BLACK, TBD	FITTING ROOMS. G.C. TO PROVIDE ADHESIVE AND INSTALLATION AS PER MANUFACTURER'S SPECIFICATIONS. DIRECT GLUE DOWN.
FG-7	G	G	CARPET	J & J INVISION	PROBLEM SOLVED 6272, COLOR 12691, FIX A FLAT	SALES FITTING ROOMS - FEATHER FINISH. G.C. TO PROVIDE ADHESIVE AND INSTALLATION AS PER MANUFACTURER'S SPECIFICATIONS. DIRECT GLUE DOWN.
FG-8	G	G	POKORAIN TILE	WAL-TILE	HEATH AND SAFFIA (A1222) 12"x12" (1212/22)	WALLS AND PARTS. EXISTING BUILDING PRODUCTS COLOR: BASS KEYS 12"x12" PRECUT TRIM. INSTALL PER MANUFACTURERS SPECS.
FC-13	O	G	WALKOFF MAT	TBD	BERBER WALK-OFF MAT	STOREFRONT ENTRY AREA (EXTERIOR STORES ONLY)
FC-14	G	G	VCT - VINYL COMPOSITION TILE	ARMSTRONG	SANDY BEACH 51223 12"x12" STANDARD EXCELON IMPERIAL TEXTURE.	NON-SALES 1/4" TURN PATTERN. CLEAN, POLISH AND WAX PRIOR TO TURNOVER. VERIFY LL REQUIREMENT FOR WATERPROOF MEMBRANE, IF REQUIRED USE LATICRETE #4236 OR APPROVED EQUAL.
FC-15	G	G	VCT - VINYL COMPOSITION TILE	ARMSTRONG	1067 LIFE 57515 12"x12" STANDARD EXCELON RAVE	NON-SALES AS REQUIRED BY CODE. CLEAR PATH AND CLEAR AREA IN FRONT OF ELECTRICAL EQUIPMENT. CLEAN, POLISH AND WAX PRIOR TO TURNOVER.
FC-16	G	G			MALL MATCH FLOORING AT ENTRY	LEASE LINE TO CLOSURE LINE
FC-17			CONCRETE		EXISTING CONCRETE	NON-SALES AREA - CONCRETE TO BE SEALED
FC-18	-	G	(E) SALES AREA FLOORING	-	(E) SALES AREA FLOORING	(E) REMAINING SALES FLOORING TILE CAN BE FOUND IN STOCK ROOM. G.C. TO INSTALL FLOORING TO MATCH EXISTING PATTERN.

WALL BASE						
B-1	O	G	WOOD	IDX	1" x 8" CLEAR POPLAR	SALES - SCRIBE TO 6" AT HIGH POINT; FINISH AS PER SPECIFICATIONS ON SHEET AS.2. MITER AT ALL CUTS; FILL AND POLISH SMOOTH ALL JOINTS
B-2	G	G	VINYL	ARMSTRONG	JET BLACK 60, 4" COVE BASE	NON-SALES & TOILET ROOM(S)
B-3	G	G	WOOD	-	1" x 4" POPLAR WOOD BASE SCRIBE TO 4" AT HIGH POINT	FITTING ROOM LOUNGE & FITTING ROOMS. G.C. TO PAINT P-3B.
B-4	G	G	WOOD	G.C.	5/8"x4" CLEAR POPLAR	BARRICADE FINISH AS PER SPECIFICATION ON SHEET A1.1

WALL TRIMS						
T-1	G	G	MDF TRIM MOLDING	EVERTRUE	LOWE'S ITEM #221744, MODEL #340R-MDFB OR EQUAL	SALES FLOOR MIRRORS - G.C. TO PRIME AND PAINT P-2B OR P-3B (REFER TO INTERIOR ELEVATIONS)
T-2	G	G	WOOD	IDX	3/4"x3 1/2" CLEAR POPLAR	FITTING ROOM LOUNGE OPENING FACE, STOREFRONT SOFFIT FACE AND FOCAL WALL SOFFIT FACE TRIM, FINISH AS PER SPECIFICATIONS ON SHEET A7.1.
T-3A	G	G	WOOD	IDX	3/4"x6" CLEAR POPLAR	FOCAL WALLS AND FITTING ROOM LOUNGE OPENING BOTTOM AND SIDE TRIM. FINISH AS PER SPECIFICATIONS ON SHEET A7.1 AND A9.2.
T-3B	G	G	WOOD	IDX	3/4"x 6" CLEAR POPLAR CUT TO REQUIREMENTS IN THE FIELD	STOREFRONT SOFFIT, BOTTOM AND SIDE TRIM. FINISH AS PER SPECIFICATIONS ON SHEET AS.4
T-4	G	G	WOOD	IDX	PROFILE 65H 0401 3-00	FITTING ROOM LOUNGE WALL TRIM. FINISH AS PER SPECIFICATIONS ON SHEET A7.1.
T-5	G	G	WOOD	-	1" x 4" FLAT STOCK POPLAR WOOD TRIM	SALES AREA. FINISH IN FIELD G.C. TO PAINT P-3A

REFER TO G/A11 FOR TRIM PROFILES.

MIRRORS						
M-1	G	G	MIRROR	G.C.	1/4" THICK MIRROR	TOILET ROOM(S), SALES, FITTING ROOM LOUNGE AND FITTING ROOMS. G.C. TO PROVIDE AND INSTALL J-BOLD, BASTIC, ETC.
M-2	G	G	MIRROR	PREMIER	OVAL MIRROR	FITTING ROOM LOUNGE AND FITTING ROOMS.
M-4	O	G	MIRROR	VASHANI	1/4" THICK MIRROR W/FRAME KIT	FITTING ROOM 36" MIRROR FRAME KIT. INSTALL PER MANUFACTURERS RECOMMENDATIONS.

STOREFRONT FINISHES						
GF-1	G	G	PORCELAIN THERMOFLEX TILE	CERAMIC TECHNIQS	FINN 353 WLP (11 3/4"x13 1/2")	ENTRY PORTAL; CUT AS NEEDED - LATICRETE UNSANDED GROUT - COLOR: #23 - ANTIQUE WHITE WITH 1/8" GROUT. PERMANENTLY REPAIR EXPOSED EDGES WHERE EXPOSED - STACKED BOND PATTERN
GF-2	G	G	PORCELAIN TILE	CERAMIC TECHNIQS	FINN 361L (11 3/4"x13 1/2")	STOREFRONT FIELD TILE; CUT AS NEEDED - G.C. TO PROVIDE LATICRETE UNSANDED GROUT - COLOR: #23 - ANTIQUE WHITE WITH 1/8" GROUT. PERMANENTLY REPAIR EXPOSED EDGES WHERE EXPOSED - STACKED BOND PATTERN
GF-3A	O	G	PORCELAIN TILE	DAL TILE	MATCHPOINT - JET BLACK UNPOLISHED (11 3/4" x 23 1/4") CUT TO FIT	STOREFRONT BORDER TRIM; CUT AS NEEDED - G.C. TO PROVIDE LATICRETE UNSANDED GROUT - COLOR: #23 - MIDNIGHT WITH 1/8" GROUT. PERMANENTLY REPAIR EXPOSED EDGES WHERE EXPOSED

NOTE:

- G.C. TO PROVIDE ALL FINISH HARDWARE (U.N.O.), NOT SUPPLIED BY OWNER, BUT NOT LIMITED TO: HINGES, LOCKSETS, CLOSURES, STOPS, THRESHOLDS, SILENCERS, WEATHER-STRIPPING, CYLINDERS MASTER-KEYED, PUSHERS, PULLS, KICK-PLATES, ETC. U.N.O.
- FOR FIRE RATED OPENINGS - PROVIDE UL TESTED AND LISTED HARDWARE ALL HARDWARE SHALL COMPLY WITH ACCESSIBILITY GUIDELINES.
- SIZE AND MOUNT UNITS TO COMPLY WITH MANUFACTURERS RECOMMENDATIONS FOR THE EXPOSURE CONDITION. REINFORCE THE SUBSTRATE AS RECOMMENDED.
- INSTALL EACH HARDWARE ITEM TO COMPLY WITH MANUFACTURER'S RECOMMENDATIONS. KEYING TO BE AS DIRECTED BY OWNER'S INSTRUCTION. PROVIDE KEYS IN QUANTITIES TO BE ESTABLISHED BY OWNER.
- ALL HAND ACTIVATED DOOR OPENING HARDWARE SHALL BE CENTERED BETWEEN 34" TO 44" A.F.F. AND SHALL BE OPERABLE WITH A SINGLE EFFORT BY LEVER TYPE HARDWARE WITHOUT MEANS OF TIGHT GRASPING, PINCHING, OR TWISTING OF THE HAND.

DOORS SHALL BE OPERABLE FROM WITHIN WITHOUT THE USE OF ANY SPECIAL KNOWLEDGE OR EFFORT WHEN THE SPACE IS OCCUPIED