NON-SALES STOCKROOM

Item	Furnished By O	Furnished By G	Furnished By L	Installed By O	Installed By G	Installed By L	E	Remarks
VCT FLOORING AND RUBBER BASE		●			●		●	
SURFACE MOUNTED STANDARDS, BRACKETS, LADDER HOOKS, CLIPS, MOUNTING HARDWARE, ETC.	●				●			
HANGROD, BRACKETS, END CAPS, CONNECTORS FOR NON-SALES	●				●			
3/4" WALL MOUNTED WOOD SHELVING		●			●			
FIXED RIVET RACK SHELVING AND HARDWARE	●				●			
MOBILE SHELVING AND HARDWARE	●				●			
MOBILE SHELVING CRANK SYSTEM	●				●			
BRUSHED STAINLESS STEEL CORNER GUARDS		●			●			REFER TO A/A13.1 PURCHASED THROUGH CBC
DRAWING PLAN TUBE							●	
MARKETING STORAGE BINS		●			●			
HARDWARE STORAGE BINS							●	
PROCESSING WORK STATION	●				●			PROVIDED BY LLS
STORAGE LEDGE SIGNAGE		●			●			
FLOORING PATCH AND REPAIR		●			●			REPLACE ANY BROKEN OR DAMAGED FLOORING

BREAK ROOMS/AREAS

REFER TO A/A13.1 FOR SPECS AND RESPONSIBILITIES

TOILET/POWDER ROOMS

REFER TO A/A13.1 FOR SPECS AND RESPONSIBILITIES

OFFICE/TRAINING ROOMS

REFER TO A/A13.1 FOR SPECS AND RESPONSIBILITIES

Item	Remarks
ELECTRICAL	
ELECTRICAL WORK (AS SPECIFIED)	SEE ELECTRICAL DRAWINGS
FIRE ALARM	
FIRE ALARM WORK (AS SPECIFIED)	SEE ELECTRICAL DRAWINGS
MECHANICAL	
MECHANICAL WORK (AS SPECIFIED)	SEE MECHANICAL DRAWINGS
PLUMBING	
PLUMBING WORK (AS SPECIFIED)	SEE PLUMBING / FIRE PROTECTION DRAWINGS
FIRE PROTECTION	
FIRE PROTECTION WORK (AS SPECIFIED)	SEE PLUMBING / FIRE PROTECTION DRAWINGS
STRUCTURAL	
STRUCTURAL WORK (AS SPECIFIED)	SEE STRUCTURAL DRAWINGS

SALES AREA - GLOBAL

Item	Furnished By O	Furnished By G	Furnished By L	Installed By O	Installed By G	Installed By L	E	Remarks
CASHWRAPS, CASHWRAP FILLERS & BACKWRAPS	●				●			FILLER AS REQUIRED
ANTI-FATIGUE MAT AT CASHWRAP	●				●			
CASHWRAP EQUIPMENT, DETAGGERS, AND SIGNATURE CAPTURE.	●			●				
FURNITURE, FIXTURES & PRESENTATION ITEMS	●				●		●	G.C. TO UNCRATE, ASSEMBLE AND CLEAN
CABINETWORK (PRE-FINISHED) & ACCESSORIES	●				●			
FINS / GABLES	●				●			
WOOD TRIMS	●				●			SEE DETAILS J/A11.1, AND K/A11.1
FABRICS AND MOUNTING HARDWARE	●				●			
WALL MOUNTED HANGBARS AND BRACKETS	●				●			
INTERIOR SIGNAGE ELEMENTS	●			●				
NEW COUNTER TOPS AT CASHWRAP AND/OR BACKWRAP	●				●			REFER TO A05.X
RECESSED STANDARD PANELS	●				●			-
SALES AREA- VSL/VSB								
BEAUTY SHELF LIGHTING	●				●			
9-NICHE FOCAL	●				●			INSTALL LOOSE FABRIC PANELS
RECESSED WALL STANDARD STUDS W/ STANDARD	●				●			
FRAMED GRAPHICS	●				●			
SCRIPT SIGNAGE VINYLS	●			●				INCLUDING BRA SALON, PANTY BOUTIQUE, FITTING ROOM, ETC.
RIBBON WRAPPED VALANCE PANELS AT BRA SALON	●				●			WITH PRE-INSTALLED HARDWARE
3/8" FINISH PANELS	●				●			STAINED, LAMINATE, OR PRIMED PANEL (SEE FINISH PLAN)
FLEX TRIM AT CURVED BRA SALON FOCAL	●				●			
DECORATIVE FLOOR LAMPS / CASHWRAP LAMPS	●				●			
DRUM SHADE	●				●			
CUP HOOKS AT VALANCES	●				●			GLUE INTO ANCHOR WHEN INSTALLED AT GYP. BD. SURFACE
BEAUTY SHELF COVERS	●				●			-
CRYSTAL KNOBS AT COLUMNS	●				●			INSTALL W/ VENDOR SUPPLIED HARDWARE
SALES AREA- PINK								
PUCK PANELS	●				●			
NEON SIGNAGE	●			●				
SUPPORT & POWER FOR NEON SIGNAGE		●			●			
BULB LETTER SIGNAGE	●			●				
CLOCK OUTLETS FOR BULB LETTER SIGNAGE	●				●			(4) INDIVIDUAL OUTLETS
SUPPORT & POWER FOR BULB LETTER SIGNAGE		●			●			
ACCESSORY CABINETS	●				●			
LARGE DECORATIVE MIRROR @ PINK BACKWRAP	●				●			INCLUDES GLASS, TRIM, BACKER AND CLEATS
PINK FOCAL CABINET	●				●			
BARRISTER CABINETS INCLUDING MIRRORED VALANCE	●				●			GLASS COMES PRE-INSTALLED
LADDER RAIL PIPE AND BRACKETS	●				●			PRE-FINISHED
BRASS HOOKS AND HARNESS HOOKS	●				●			
MARKETING PIPE RAILS - PIPES AND FITTINGS		●			●			G.C. TO FIELD PAINT
BARRISTER CABINET MIRRORED TRANSOM AT FITTING ROOM / ALCOVE TRANSITION	●				●			GLASS COMES PRE-INSTALLED
PINK TRANSITION BEAUTY NICHE CABINET	●				●			
BACKWRAP CUBBIES	●				●			
DECORATIVE SALES FLOOR MIRROR: INCLUDES GLASS, PLYWOOD BACKER, J-CHANELS, MASTIC, AND Z-CLIPS	●				●			DOOR AND TRANSITION MIRRORS NOT INCLUDED
FITTING ROOMS- GLOBAL								
FITTING ROOM SEATING	●				●			
ALL FITTING ROOM TRIM							●	
ACCESSIBLE SIGN							●	AT ACCESSIBLE FITTING ROOM ONLY
PAPER PANTY HOLDER	●				●			
FITTING ROOMS- VSL								
FITTING ROOM MIRROR DECORATIVE FRAME, MOUNTING FRAME, BACK PANEL, AND GLASS	●				●			G.C. TO PROVIDE BLOCKING
RUGS	●				●			
PAINTED STEEL CORNER GUARDS		●			●			G.C. TO PAINT TO MATCH WALL SURFACE.
FLEX TRIM AT CURVED WALLS	●				●			
FITTING ROOM HOOKS	●				●			G.C. TO PROVIDE BLOCKING
GO BACK NICHE/CLOSET							●	
GO BACK RACK							●	
FREESTANDING BRA WARDROBER							●	
FITTING ROOMS- PINK								
WALLCOVERING GRAPHIC PANELS	●				●			SEE SHEET A10.05 AND J/A10.06
FITTING ROOM MIRROR: LADDER FRAME, PLY BACKER, J-CHANNELS, SUB-FRAME, AND DECORATIVE FRAME	●				●			
FITTING ROOM MIRROR GLASS, MASTIC AND PRIMER		●			●			
BUILT-IN BRA WARDROBER	●				●			
OUTFITTING CENTER	●				●			
WINDOW TRANSOM AT TRANSITION FROM VESTIBULE TO FITTING ROOM ALCOVE	●				●			
FITTING ROOM BENCH PEW	●				●			
PINK FITTING ROOM HOOKS	●				●			G.C. TO PROVIDE BLOCKING
PINK FITTING ROOM STENCIL	●				●			APPLY TO TRIM IN FIELD PER VENDOR INSTRUCTIONS
FIT CARD HOLDER	●				●			

STOREFRONT- GLOBAL

Item	Furnished By O	Furnished By G	Furnished By L	Installed By O	Installed By G	Installed By L	E	Remarks
EXTERIOR WATERPROOFING AND FLASHING		●			●			
STOREFRONT SIGNAGE	●			●				
BLADE SIGN	●			●				BLOCKING BY G.C.
STOREFRONT AWNINGS	●			●				BLOCKING BY G.C.
STOREFRONT BANNER	●			●				BLOCKING BY G.C.
DISPLAY WINDOW HANGING GRAPHICS	●				●			
IN-WALL BATT INSULATION		●			●			
STOREFRONT STRUCTURAL MEMBERS		●			●			SEE STRUCTURAL DRAWINGS
MALL FLOORING AT STOREFRONT		●			●			SEE FLOOR AND WALL FINISH PLAN
WALK-OFF ENTRY MAT		●			●			SEE SPECIFICATIONS SECTION 124813
CONCRETE SIDEWALK							●	PER LL REQUIREMENTS
CONCRETE SIDEWALK PATCH AND REPAIR		●			●			AS REQUIRED
UV PROTECTION FILM		●			●			REFER TO SPECIFICATIONS SECTION 088100
IMPACT RESISTANT METAL MULLIONS		●			●			FOR USE IN HURRICANE ZONES
LAMINATED METAL PANELS	●				●			G.C. TO FIELD FIT
STOREFRONT PLASTER FINISH							●	REFER TO A08.X
TOUCH-UP FINISHES AT STOREFRONT		●			●			REFER TO A08.X
STOREFRONT EIFS FINISH	●				●			REFER TO A08.X
STOREFRONT- VSL								
PRE-FINISHED METAL TRIM / DECORATIVE PROFILES	●			●				
PRE-FINISHED BREAK METAL	●			●				
PRE-FINISHED METAL BASE	●			●				
PRE-FINISHED METAL PANELS W/ BACKER	●			●				
PRE-FINISHED METAL ACCESS PANEL AT PLATFORM FLOOR	●			●				
PRE-FINISHED METAL ACCESS PANEL AT PORTAL	●			●				
RECESSED LIGHT FIXTURE AT PORTAL ACCESS PANEL	●				●			
PRE-FINISHED METAL MULLIONS	●			●				
STOREFRONT GLAZING	●			●				VSL SIDE ONLY
SEALANT AT GLASS JOINTS	●			●				
MILK WHITE POLYCARBONATE W/ PRINTED GRAPHIC SURFACES	●			●				
CLEAR ACRYLIC ANGLES FOR SECURING POLYCARB	●			●				APPLIED TO ALL FOUR SIDES OF GLASS
STOREFRONT LED LIGHT FIXTURES	●				●			
DIMMER SYSTEM	●				●			
VERTICAL ACCESS PANELS AT DISPLAY WINDOW SOFFIT		●			●			FOR LED ACCESS
MARKETING GRID	●				●			
WINDOW LIGHT BOX TOWER (LBTXX)	●				●			G.C. TO ASSEMBLE, SEE ELECTRIC DWGS FOR POWER.
WALL MOUNTED LIGHTBOX (LBWXX)	●				●			G.C. TO ASSEMBLE, SEE ELECTRIC DWGS FOR POWER.
PRE-FINISHED GLAZING MINI MALL CLAMP	●			●				
REVEALS AT NEUTRAL PIERS & BULKHEAD							●	VSL SIDE ONLY WHEN REQUIRED
STONE STOREFRONT: QUARTZ AGGLOMERATE	●				●			G.C. TO PROVIDE PLYWOOD & STRUCTURE
STONE STOREFRONT: SUPPORT SYSTEM (INCLUDING CLIPS, CHANNELS/ANGLES, AND FASTENERS)	●				●			G.C. TO ASSEMBLE PER VENDOR INSTRUCTIONS
STONE STOREFRONT: EPOXY (FOR ATTACHMENT OF ANCHORS INTO PRE-DRILLED HOLES)		●			●			G.C. TO ASSEMBLE PER VENDOR INSTRUCTIONS
STONE STOREFRONT: GROUT/CAULK	●				●			G.C. TO ASSEMBLE PER VENDOR INSTRUCTIONS
CEILING ACCESS PANEL AT WOOD LINER		●			●			
LUMISHEET AND APPLIED VINYL AT DISPLAY WINDOWS	●			●				POWER BY G.C.
PORTAL SIGN BOX	●			●				POWER AND BLOCKING BY G.C.
STOREFRONT- PINK								
MARKETING PIPE RAILS - PIPES AND FITTINGS		●			●			G.C. TO FIELD PAINT
GRAPHIC PAINTED ON TO ROLLING GRILLE	●			●				
PINK SIGNAGE: PRE-FINISHED PLANKS	●				●			ASSEMBLE PER MFG. INSTRUCTIONS
PINK SIGNAGE: "PINK" LETTERS	●			●				
WOOD WINDOW MULLIONS	●				●			PRE-PRIMED, PAINTED BY G.C.
FORMGLAS BASE	●				●			G.C. TO FILL ALL SEAMS WITH BONDO
HEX TILE AT PINK STOREFRONT ENTRY	●				●			THINSET AND GROUT BY G.C.
PRE-FINISHED PINK WOOD PLANK PANEL (W/ DOG) AND PRIMED EDGE TRIM ABOVE WINDOWS	●				●			ASSEMBLE PER MFG. INSTRUCTIONS
SIDE ENTRY PANEL (GRAPHIC AND TRIM)	●				●			PREFINISHED
STOREFRONT GLAZING		●			●			PINK SIDE ONLY
WINDOW VINYL LOGO AND BORDER	●			●				
THIN BRICK, MORTAR AND INSTALLATION ACCESSORIES	●				●			
DECORATIVE PAINT BRICK FINISH	●			●				
ROUND PILASTER TRIM (AND 5" DOG)	●				●			
REVEALS AT NEUTRAL PIERS & BULKHEAD		●			●			PINK SIDE ONLY WHEN REQUIRED
1/4" (MASONITE) AND 3/4" HDF PANELS		●			●			
BLIND DOOR MIRROR: LADDER FRAME, PLY BACKER, J-CHANNELS, SUB-FRAME, AND DECORATIVE FRAME	●				●			
BLIND DOOR MIRROR GLASS, MASTIC AND PRIMER		●			●			

GENERAL

Item	Furnished By O	Furnished By G	Furnished By L	Installed By O	Installed By G	Installed By L	E	Remarks
GYPSUM BOARD: CEILINGS, WALLS, ETC. AND REQUIRED FRAMING & BLOCKING		●			●		●	SEE SPECIFICATIONS SECTION 092900 & 092950
CONCEALED IN-WALL WOOD OR METAL BLOCKING FOR ALL ITEMS IN STORE		●			●		●	F.R.T. AS REQUIRED
PAINT		●			●		●	
DOORS, FRAMES & HARDWARE								SEE DOOR SCHEDULE A/A00.02
DOOR CHIMES	●				●		●	
LAY-IN CEILING (TILE & GRID)		●			●		●	SEE SPECIFICATIONS SECTION 095123
FIRE EXTINGUISHERS		●			●		●	SEE SPECIFICATIONS
EXIT & EMERGENCY LIGHTS	●				●			
CEILING AND WALL ACCESS PANELS		●			●		●	SEE SPECIFICATIONS SECTION 083100
FIBERGLASS REINFORCED PANELS (F.R.P.)							●	
ALL FURRING		●			●		●	
FLOOR PROTECTION DURING CONSTRUCTION		●			●			1/8" MASONITE
SAW CUTTING / TRENCHING/ CORE DRILLING		●			●			WHERE REQUIRED PER EQUIPMENT SPECIFIED
MUSIC / VIDEO SYSTEM SUPPORT							●	
IP CAMERA CABINET SUPPORT		●			●			
SECURITY MONITOR STRUCTURAL SUPPORT		●			●			
SECURITY DOMES							●	
ZINC DIVIDER STRIP		●			●			
STUB-UP PRE-WIRING		●			●			
ALL MIRRORS		●			●		●	UNLESS OTHERWISE NOTED
MIRROR J-CHANNELS AND BACKING		●			●		●	UNLESS OTHERWISE NOTED
MIRROR MASTIC		●			●		●	
TILE FLOORING AND WALL FINISHES	●				●		●	
ALL NATURAL STONE FINISHES	●				●		●	
GROUT, SEALANT, THINSET, AND MORTAR		●			●		●	UNLESS OTHERWISE NOTED
DEMISING WALL FRAMING							●	
DEMISING WALL GYP. BD.							●	
FLOOR PREPARATION & LEVELING		●			●			AS REQUIRED
CONCRETE SLAB		●			●		●	AS REQD, COORDINATE W/ LANDLORD
FIRE PATCHING / FIREPROOFING		●			●			AS REQD BY CODE / TENANT CRITERIA
WALL COVERINGS	●				●			
WOOD FLOORING	●				●			SEE SPECIFICATIONS SECTION 096429
WOOD FLOORING VAPOR BARRIER AND ADHESIVE		●			●			SEE SPECIFICATIONS SECTION 096429
WOOD FLOORING MOISTURE TEST		●			●			SEE SPECIFICATIONS SECTION 096429
EXPANSION JOINT COVERS		●			●			
CURTAIN TRACK, FABRIC, AND TIE-BACK HOOK	●				●			
CARPET	●				●			
CARPET BINDER BAR EDGE STRIPS		●			●			
CARPET SHIELD		●			●			
CUSTOM GROUT FOR: CHERRY BERRY AND ROSSO LEVANTO	●				●			
SOUND ATTENUATION INSULATION		●			●			SEE WALL SCHEDULE
LIGHT FIXTURES AND LAMPS		●			●		●	REFER TO ELECTRICAL DRAWINGS
LAMPS FOR ALL EXISTING LIGHT FIXTURES		●			●			REFER TO ELECTRICAL DRAWINGS
DEMOLITION (INC: BARRICADE AND PHASING)								
BARRICADE PANEL (STRUCTURE)		●			●			
GRAPHICS AND LOGOS, PACKAGE I & PACKAGE I+	●			●				REQUIRES L.L. APPROVAL
GRAPHICS AND LOGOS, PACKAGE II	●				●			REQUIRES L.L. APPROVAL
PAINT FINISH		●			●			
TEMPORARY POWER SETUP		●			●			
DE-INSTALLATION AND DE-BRANDING		●			●			SEE P/A00.00
BARRICADE REMOVAL					●			
CHAIN LINK FENCE (IF REQUIRED)		●			●			
SURFACE MOUNTED STANDARDS FOR PHASED STORES	●				●			
TEMPORARY PRE-FAB FITTING ROOMS FOR PHASED STORES	●				●			

RESPONSIBILITY SCHEDULE

ANNOTATIONS: O: OWNER (LIMITED BRANDS OR VENDOR) G: GENERAL CONTRACTOR L: LANDLORD E: EXISTING

NO SCALE

05N-A001-A00-NOTE

A

Stantec
Stantec Architecture Inc.
1383 N. McDowell Blvd., Suite 250
Petaluma, CA U.S.A. 94954
Tel. 707.765.1660 Fax. 707.765.9908
www.stantec.com

Limitedbrands
LIMITED STORE PLANNING, INC.
d/b/a STORE DESIGN & CONSTRUCTION
Three Limited Parkway · Columbus, Ohio 43230
Telephone: 614.415.7000 · Fax: 614.415.7349

PROHIBITION ON REUSE:
THESE DRAWINGS AND SPECIFICATIONS WERE PREPARED FOR USE ON A SPECIFIC SITE CONTEMPORANEOUSLY WITH THEIR ISSUE DATE. THEY ARE NOT INTENDED FOR USE ON A DIFFERENT PROJECT SITE OR AT A LATER TIME. REUSE OF THESE DRAWINGS AND SPECIFICATIONS, OR ANY REPRODUCTION THEREOF, ON ANOTHER PROJECT IS PROHIBITED AND CONTRARY TO LAW UNLESS EXPRESSLY AUTHORIZED IN WRITING BY LIMITED STORE PLANNING, INC., D/B/A LIMITED STORE DESIGN AND CONSTRUCTION ("LSDC").

THESE DRAWINGS AND SPECIFICATIONS ARE THE PROPERTY OF LSDC AND SHALL NOT BE DISPLAYED IN ANY MANNER OR USED ON ANY OTHER PROJECT EXCEPT BY WRITTEN AGREEMENT WITH LSDC. NO REPRODUCTION OF THESE DRAWINGS AND SPECIFICATIONS SHALL BE MADE WITHOUT THE WRITTEN AUTHORIZATION OF THE LSDC. ALL ORIGINALS OR REPRODUCTIONS OF THESE DRAWINGS AND SPECIFICATIONS MUST BE RETURNED TO LSDC UPON COMPLETION OF THEIR INTENDED USE, UNLESS OTHERWISE AGREED BY THE LSDC.

COPYRIGHT NOTICE:
THESE DRAWINGS AND SPECIFICATIONS ARE COPYRIGHTED AND SUBJECT TO COPYRIGHT PROTECTION AS AN "ARCHITECTURAL WORK" UNDER SEC. 102 OF THE COPYRIGHT ACT, 17 U.S.C. AS AMENDED DECEMBER 1990; KNOWN AS THE ARCHITECTURAL WORKS COPYRIGHT PROTECTION ACT OF 1990. THE PROTECTION INCLUDES, WITHOUT LIMITATION, THE OVERALL FORM, ARRANGEMENT AND COMPOSITION OF SPACES, AND ELEMENTS OF THE DESIGN. UNDER SUCH PROTECTION, UNAUTHORIZED USE OF THESE DRAWINGS AND SPECIFICATIONS MAY RESULT IN CESSATION OF CONSTRUCTION, BUILDING SEIZURE, AND/OR MONETARY LIABILITY.

010500133

PROJECT INFORMATION:
VICTORIA'S SECRET
QUAIL SPRINGS MALL
SPACE NO. 119
2501 WEST MEMORIAL RD.
OKLAHOMA CITY, OK 73134

SCOPE: OPTIMIZATION | PACKAGE: II
DESIGN TYPE: NMA/FORUM AA1 | GENERATION: R131Sa/142Fa
LSD&C PROJECT #: 00060919 | A/E PROJECT #: 2007684006

REVISIONS:
REQUIRED BY: DATE

ELITE CONSTRUCTION GROUP
LAKE JACKSON, TX
PHONE: 979-285-0712
NOTE: THESE PRINTS HAVE BEEN REDUCED BY 50 PERCENT. SCALE WILL BE 50 PERCENT OF WHAT IS NOTED ON PLANS

DATE ISSUED: 05.30.2014
DESIGNED BY: KW
DRAWN BY: MS
CHECKED BY: DB/BV

RESPONSIBILITY SCHEDULE

DRAWING NUMBER:
A00.1