

12. HOME RUN TO VIDEO DRIVER CABINET.
13. JUNCTION BOX INSTALLED AT 48" A.F.F. WITH FACE FLUSH TO DRYWALL AND 1/2" CONDUIT UP WALL TO WALL ABOVE CEILING FOR TEMPERATURE T-STAT(S)/SENSOR(S). COORDINATE EXACT REQUIREMENTS WITH MECHANICAL CONTRACTOR. MECHANICAL CONTRACTOR SHALL INSTALL L5D&C FURNISHED CONTROL CABLE FROM JUNCTION BOX TO HVAC UNITS.
14. MECHANICAL CONTRACTOR SHALL FURNISH AND INSTALL AIR DEVICE OR ACCESS PANEL TO BE USED AS ACCESS TO EQUIPMENT LOCATED ABOVE THE CEILING. THIS CONTRACTOR SHALL BE RESPONSIBLE TO ENSURE THAT A MINIMUM UNOBSTRUCTED FREE AREA OF 3-FEET VERTICALLY AND 3-FEET HORIZONTALLY IN ALL DIRECTIONS AROUND EQUIPMENT IS MAINTAINED TO ALLOW FOR INSTALLATION AND MAINTENANCE OF EQUIPMENT. IF THIS FREE AREA CANNOT BE OBTAINED, CONTACT THE L5D&C'S PROJECT MANAGER IMMEDIATELY.
15. 20" AMP RECEPTACLE - 42" A.F.F. FOR MICROWAVE. IF PLAN LOCATION IS NOT ACCEPTABLE, IMMEDIATELY CONTACT L5D&C PROJECT MANAGER FOR DIRECTION. SEE SHEET A-14.02 FOR ADDITIONAL INFORMATION.
16. 20" AMP RECEPTACLE - 18" A.F.F. FOR REFRIGERATOR. IF PLAN LOCATION IS NOT ACCEPTABLE, IMMEDIATELY CONTACT L5D&C PROJECT MANAGER FOR DIRECTION. SEE SHEET A-14.02 FOR ADDITIONAL INFORMATION.
17. JUNCTION BOX FOR WATER HEATER ELECTRICAL CONNECTION. FURNISH AND INSTALL CODE REQUIRED DISCONNECT SWITCH. COORDINATE EXACT LOCATION AND RELATED REQUIREMENTS WITH PLUMBING CONTRACTOR PRIOR TO WORK COMMENCEMENT.
18. JUNCTION BOX MOUNTED AT 42" A.F.F. FOR HAND-DRYER ELECTRICAL CONNECTION (FOR PUBLIC ACCESSIBLE RESTROOMS ONLY). COORDINATE EXACT LOCATION WITH ARCHITECT AND L5D&C PROJECT MANAGER PRIOR TO WORK COMMENCEMENT.
19. DUCT MOUNTED SMOKE DETECTOR. ELECTRICAL CONTRACTOR TO CONNECT DETECTOR TO FIRE ALARM PANEL IN SPACE.
20. KEYPAD FOR SECURITY SYSTEM, MOUNTED AT 54" A.F.F., AND 6" MIN FROM CENTERLINE OF J-BOX TO ANY CONFLICTING ITEM ON THE WALL. COUNT ON HANDLE-SIDE OF THE NON-SALES DOOR LEADING TO THE SALES AREA, WITH 3/4" CONDUIT FROM JUNCTION BOX TO ABOVE CEILING.
21. MOTION DETECTOR TO BE INSTALLED AT EACH ENTRY/ROFFING GRILLE, EVERY EXIT DOOR, ABOVE EVERY CASHWAP, AND IN THE NON-SALES CEILING CLOSE TO THE NON-SALES/SALES DOOR. VERIFY EXACT LOCATIONS WITH L5D&C PROJECT MANAGER PRIOR TO WORK COMMENCEMENT.
22. JUNCTION BOX AND CODE REQUIRED DISCONNECT SWITCH FOR MOTORIZED ROLL-UP GRILLE ELECTRICAL CONNECTION. COORDINATE EXACT LOCATION AND RELATED REQUIREMENTS WITH L5D&C PROJECT MANAGER PRIOR TO WORK COMMENCEMENT.
23. QUADRAPLEX RECEPTACLE, DUPLEX RECEPTACLE, AND COVERPLATES FOR CCTV. SEE DETAIL A/E04.02 COORDINATE EXACT LOCATION WITH ARCHITECT PRIOR TO ROUGH-IN AND WORK COMMENCEMENT.
24. DUPLEX RECEPTACLE WITH COVERPLATE AND JUNCTION BOX INSTALLED ON CEILING FOR CCTV SYSTEM VIEW MONITOR. COORDINATE EXACT LOCATION. SEE SHEET A-04.01/42.03.

- 4) PROVIDE 1/2" EMPTY CONDUIT WITH PULL STRING BACK TO IP CAMERA CABINET.
- 5) PROVIDE 1/2" EMPTY CONDUIT WITH PULL STRING TO DATA-SECTION OF IFS-PANEL.
- 6) QUADRAPLEX IS RECEPTACLES, AND COVERS/FATES FOR IP CAMERA SYSTEM. SEE DETAIL K/E04.02 COORDINATE EXACT LOCATION WITH ARCHITECT PRIOR TO ROUGH-IN AND WORK COMMENCEMENT.
- 7) PROVIDE JUNCTION BOX AT 60" AFF. FOR VOLUME CONTROL. PROVIDE 1/2" EMPTY CONDUIT WITH PULL STRING TO MUSIC SYSTEM AT MANAGER'S DESK.
- 8) PROVIDE JUNCTION ABOVE CEILING FOR DRINKING FOUNTAIN CHILLER. COORDINATE REQUIREMENT WITH PLUMBING CONTRACTOR.

NTS	D
0201-D00-NOTE	11/11/11



1/4" = 1'-0"	A

REVISIONS:		
	REQUIRED BY:	DATE
1	STOREFRONT REVISION - REV 1	6/10/20
2	REVISION 2 - L.L. / PERMIT COMMENTS	6/27/20

DATE ISSUED: 04/11/201  
DESIGNED BY: PF  
DRAWN BY: PF  
CHECKED BY: TW

DRAWING NUMBER:

E02.01